

**BUILT-UP AIR HANDLING UNIT SCHEDULE**

UNIT NO.	LOCATION	SERVICE	TYPE	SUPPLY AIR FAN *	CHILLED WATER COIL *	HEATING COIL *	HUMIDIFIER *	FILTER *	AIR FLOW		REMARKS
									SUPPLY AIR CFM	OUTSIDE AIR CFM	
W-CS-107-AH-03	LVEA BUILDING	OSB (LAB)	BUILT-UP	W-CS-107-SF-05 W-CS-107-SF-06	W-CS-107-CC-05 W-CS-107-CC-06	W-CS-107-HC-09 W-CS-107-HC-10	W-CS-107-HU-05 W-CS-107-HU-06	W-CS-107-AF-03	24,000	1,720	CONTRACTOR WILL SUBMIT SHOP DRAWINGS SHOWING CONSTRUCTION DETAILS FOR APPROVAL
W-MA-203-AH-01	MID STATION A	MID STATION A	BUILT-UP	W-MA-203-SF-01 W-MA-203-SF-02	W-MA-203-CC-01 W-MA-203-CC-02	-----	W-MA-203-HU-01 W-MA-203-HU-02	W-MA-203-AF-01 W-MA-203-AF-02	13,200	840	CONTRACTOR WILL SUBMIT SHOP DRAWINGS SHOWING CONSTRUCTION DETAILS FOR APPROVAL
W-MB-203-AH-01	MID STATION B	MID STATION B	BUILT-UP	W-MB-203-SF-01 W-MB-203-SF-02	W-MB-203-CC-01 W-MB-203-CC-02	-----	W-MB-203-HU-01 W-MB-203-HU-02	W-MB-203-AF-01 W-MB-203-AF-02	13,200	840	CONTRACTOR WILL SUBMIT SHOP DRAWINGS SHOWING CONSTRUCTION DETAILS FOR APPROVAL
W-EA-203-AH-01	END STATION A	END STATION A	BUILT-UP	W-EA-203-SF-01 W-EA-203-SF-02	W-EA-203-CC-01 W-EA-203-CC-02	-----	W-EA-203-HU-01 W-EA-203-HU-02	W-EA-203-AF-01 W-EA-203-AF-02	13,200	840	CONTRACTOR WILL SUBMIT SHOP DRAWINGS SHOWING CONSTRUCTION DETAILS FOR APPROVAL
W-EB-203-AH-01	END STATION B	END STATION B	BUILT-UP	W-EB-203-SF-01 W-EB-203-SF-02	W-EB-203-CC-01 W-EB-203-CC-02	-----	W-EB-203-HU-01 W-EB-203-HU-02	W-EB-203-AF-01 W-EB-203-AF-02	13,200	840	CONTRACTOR WILL SUBMIT SHOP DRAWINGS SHOWING CONSTRUCTION DETAILS FOR APPROVAL

**NOTES:**

1. FOR LEGEND, ABBREVIATIONS AND GENERAL NOTES SEE SHEETS WA-H-001 AND WA-H-002.

\* SEE INDIVIDUAL EQUIPMENT SCHEDULES

**PACKAGED AIR-COOLED WATER CHILLER SCHEDULE**

UNIT NO.	LOCATION	SERVICE	TYPE	CHILLED FLUID	AMBIENT		COMPRESSOR		MINIMUM CAPACITY (TONS)	MAX KW	REFRIGERANT	EVAPORATOR		CONDENSER		SINGLE POINT ELECT CONN			OPER WT (LB)	MANUFACTURER/ MODEL NO.	REMARKS			
					DESIGN TEMP (*F DB)	ALTITUDE (FT)	MIN OPER TEMP (*F DB)	TYPE				DRIVER	ENT TEMP (*F)	LVG TEMP (*F)	GPM	MAX PD (FT)	NO. FANS EACH UNIT	HP EACH FAN				VOLTS/ PH/Hz	TOTAL RLA	TOTAL LRA
W-MA-200-CH-01	MID STATION A	MID STATION A	AIR COOLED	WATER 40% GLYCOL	105	400	0°F	SCREW	ELECT MOTOR	55	77	R-22	54.8	42	105	15	8	1.1	460/3/60	112	229	4950	TRANE RTAA 70	ALL PERFORMANCE DATA ARE AT ACTUAL CONDITIONS, LOW AMBIENT (-10°F)
W-MA-200-CH-02	MID STATION A	MID STATION A	AIR COOLED	WATER 40% GLYCOL	105	400	0°F	SCREW	ELECT MOTOR	55	77	R-22	54.8	42	105	15	8	1.1	460/3/60	112	229	4950	TRANE RTAA 70	ALL PERFORMANCE DATA ARE AT ACTUAL CONDITIONS, LOW AMBIENT (-10°F), STANDBY
W-MB-200-CH-01	MID STATION B	MID STATION B	AIR COOLED	WATER 40% GLYCOL	105	400	0°F	SCREW	ELECT MOTOR	55	77	R-22	54.8	42	105	15	8	1.1	460/3/60	112	229	4950	TRANE RTAA 70	ALL PERFORMANCE DATA ARE AT ACTUAL CONDITIONS, LOW AMBIENT (-10°F)
W-MB-200-CH-02	MID STATION B	MID STATION B	AIR COOLED	WATER 40% GLYCOL	105	400	0°F	SCREW	ELECT MOTOR	55	77	R-22	54.8	42	105	15	8	1.1	460/3/60	112	229	4950	TRANE RTAA 70	ALL PERFORMANCE DATA ARE AT ACTUAL CONDITIONS, LOW AMBIENT (-10°F), STANDBY
W-EA-200-CH-01	END STATION A	END STATION A	AIR COOLED	WATER 40% GLYCOL	105	400	0°F	SCREW	ELECT MOTOR	55	77	R-22	54.8	42	105	15	8	1.1	460/3/60	112	229	4950	TRANE RTAA 70	ALL PERFORMANCE DATA ARE AT ACTUAL CONDITIONS, LOW AMBIENT (-10°F)
W-EA-200-CH-02	END STATION A	END STATION A	AIR COOLED	WATER 40% GLYCOL	105	400	0°F	SCREW	ELECT MOTOR	55	77	R-22	54.8	42	105	15	8	1.1	460/3/60	112	229	4950	TRANE RTAA 70	ALL PERFORMANCE DATA ARE AT ACTUAL CONDITIONS, LOW AMBIENT (-10°F), STANDBY
W-EB-200-CH-01	END STATION B	END STATION B	AIR COOLED	WATER 40% GLYCOL	105	400	0°F	SCREW	ELECT MOTOR	55	77	R-22	54.8	42	105	15	8	1.1	460/3/60	112	229	4950	TRANE RTAA 70	ALL PERFORMANCE DATA ARE AT ACTUAL CONDITIONS, LOW AMBIENT (-10°F)
W-EB-200-CH-02	END STATION B	END STATION B	AIR COOLED	WATER 40% GLYCOL	105	400	0°F	SCREW	ELECT MOTOR	55	77	R-22	54.8	42	105	15	8	1.1	460/3/60	112	229	4950	TRANE RTAA 70	ALL PERFORMANCE DATA ARE AT ACTUAL CONDITIONS, LOW AMBIENT (-10°F), STANDBY

**CHILLED WATER COOLING COIL SCHEDULE**

UNIT NO.	LOCATION	SERVICE	TOTAL CAPACITY (MBH)	SENSIBLE CAPACITY (MBH)	MAX FACE VEL (FFM)	ACFM	MAX AIR PD (IN. WG)	ROWS	EAT			LWT (*F)	LWT (*F)	GPM	MAX WTR PD (FT)	MANUFACTURER/ MODEL NO.	OVERALL SIZE (IN. X IN.)	REMARKS		
									*FDB	*FWB	*FDB *FWB									
W-CS-107-CC-05	CORNER STATION	OSB	393	387	445	11,500	0.60	8	8	83.1	62.7	50.9	50	42	50	95	15	COLMAC DX	36 X 105	40% GLYCOL
W-CS-107-CC-06	CORNER STATION	OSB	393	387	445	11,500	0.60	8	8	83.1	62.7	50.9	50	42	50	95	15	COLMAC DX	36 X 105	40% GLYCOL
W-MA-203-CC-01	MID STATION A	MID STATION A	418	414	460	11,400	0.75	8	11	86.7	63.7	51	49.9	42	52.8	95	10	COLMAC DX	2(30 X 60)	40% GLYCOL
W-MA-203-CC-02	MID STATION A	MID STATION A	418	414	460	11,400	0.75	8	11	86.7	63.7	51	49.9	42	52.8	95	10	COLMAC DX	2(30 X 60)	40% GLYCOL
W-MB-203-CC-01	MID STATION B	MID STATION B	418	414	460	11,400	0.75	8	11	86.7	63.7	51	49.9	42	52.8	95	10	COLMAC DX	2(30 X 60)	40% GLYCOL
W-MB-203-CC-02	MID STATION B	MID STATION B	418	414	460	11,400	0.75	8	11	86.7	63.7	51	49.9	42	52.8	95	10	COLMAC DX	2(30 X 60)	40% GLYCOL
W-EA-203-CC-01	END STATION A	END STATION A	418	414	460	11,400	0.75	8	11	86.7	63.7	51	49.9	42	52.8	95	10	COLMAC DX	2(30 X 60)	40% GLYCOL
W-EA-203-CC-02	END STATION A	END STATION A	418	414	460	11,400	0.75	8	11	86.7	63.7	51	49.9	42	52.8	95	10	COLMAC DX	2(30 X 60)	40% GLYCOL
W-EB-203-CC-01	END STATION B	END STATION B	418	414	460	11,400	0.75	8	11	86.7	63.7	51	49.9	42	52.8	95	10	COLMAC DX	2(30 X 60)	40% GLYCOL
W-EB-203-CC-02	END STATION B	END STATION B	418	414	460	11,400	0.75	8	11	86.7	63.7	51	49.9	42	52.8	95	10	COLMAC DX	2(30 X 60)	40% GLYCOL

**EXPANSION TANK SCHEDULE**

UNIT NO.	LOCATION	SERVICE	TYPE	MIN CAP (GAL)	MAX WORKING PRESS (PSIG)	MAX OPER TEMP (*F)	OPER WT (LB)	MANUFACTURER/ MODEL NO.	REMARKS
W-MA-203-TK-01	MID STATION A	CHILLED WATER	DIAPHRAM	23	150	110	285	EXTROL EX 60	
W-MB-203-TK-01	MID STATION B	CHILLED WATER	DIAPHRAM	23	150	110	285	EXTROL EX 60	
W-EA-203-TK-01	END STATION A	CHILLED WATER	DIAPHRAM	23	150	110	285	EXTROL EX 60	
W-EB-203-TK-01	END STATION B	CHILLED WATER	DIAPHRAM	23	150	110	285	EXTROL EX 60	

**AIR SEPARATOR SCHEDULE**

UNIT NO.	LOCATION	SERVICE	MIN CAP (GPM)	SIZE (IN.)	OPER WT (LB)	MANUFACTURER/ MODEL NO.	REMARKS
W-MA-203-AS-01	MID STATION A	CHILLED WATER	170	3"	200	BELL & GOSSETT R-3	
W-MB-203-AS-01	MID STATION B	CHILLED WATER	170	3"	200	BELL & GOSSETT R-3	
W-EA-203-AS-01	END STATION A	CHILLED WATER	170	3"	200	BELL & GOSSETT R-3	
W-EB-203-AS-01	END STATION B	CHILLED WATER	170	3"	200	BELL & GOSSETT R-3	

This document and the design it covers are the property of PARSONS. They are loaned only with the borrower's expressed written agreement that they will not be reproduced, copied, loaned, exhibited, or used in any other way, except by written consent from PARSONS to the borrower.

ISSUED FOR CONSTRUCTION		CLP	6-24-96
DRAWN			
CHECKED			
ENGINEER			
PROJ			
<b>AS-BUILT DRAWINGS</b>			
ISSUED FOR AS-BUILT			
NO.	DATE	BY	DESCRIPTION
1	5-15-98	CP	



**LIGO-D960345-01-0**

LASER INTERFEROMETER  
GRAVITATIONAL-WAVE OBSERVATORY  
SITE NO. 1 - HANFORD, WASHINGTON

TITLE	HVAC EQUIPMENT SCHEDULES SHEET 1	SCALE	NONE	CONTRACT NUMBER	PP150969	PROJECT NUMBER	8094
SHEET NUMBER	<b>WA-H-003</b>	REVISIONS					