

**Laser Interferometer Gravitational - Wave Observatory**  
**Ligo**  
**Tube Bake Out**  
**Bill of Materials - LIGO-D980055-C-W**  
**Assembly "A2"**  
**Portable 120/208 Volt, 3 Phase Service Assembly**

<b>Item Num.</b>	<b>Description</b>	<b>Manufacturer</b>	<b>Part No.</b>	<b>Req.</b>	<b>Unit</b>	<b>Material</b>	<b>Labor</b>
A2-1	120/208V, 225A Panel 'A2'	See drawing D980056	Sub-Assembly 'A2-1'	1	lot	LIGO	Contractor
001	Unistrut frame	See drawing D980053	Assembly	1	lot	Contractor	Contractor
008	Amber Caution Light	Federal	Model 141ST	1	ea.	LIGO	Contractor
022	Service Entrance Conductor	See drawing D980053	#1/0 CU Per NEC	1	lot	Contractor	Contractor
023	Grounding	As Required	Requirements	1	lot	Contractor	Contractor
025	Seal Tight Flex	See drawing D980053	1 1/2"	1	lot	Contractor	Contractor
026	45 KVA, Three Phase Dry- Type Transformer	Cutler Hammer	V48M28T45K	1	ea.	Contractor	Contractor
027	4 Wire, #4 Ga. Portable Power Cord, 600V, 60A, Type SO	Anixter	4A-0404	25	ft.	Contractor	Contractor
028	480V, 60A 4 Wire Plug	Hubbell	560P7W	1	ea.	Contractor	Contractor