


**LIGO LABORATORY**  
California Institute of Technology  
Massachusetts Institute of Technology

**National Science Foundation  
Review of Advanced LIGO  
June 11-13, 2003  
Pasadena, California**



# **LIGO LABORATORY**

**California Institute of Technology/Massachusetts Institute of Technology**

**National Science Foundation  
Review of Advanced LIGO  
June 11-13, 2003  
Pasadena, California**

## **TABLE OF CONTENTS**

### **I. Introduction**

Charge to the Committee

Agenda

Glossary of Acronyms and Abbreviations

### **II. Presentations**

LIGO Overview	Gary Sanders
Initial LIGO Commissioning & First Observations	Stan Whitcomb
Astrophysics	Kip Thorne
Overview of Advanced LIGO	David Shoemaker
Cost, Schedule, Management	Gary Sanders



## **Charge to the Review Panel**

The NSF Grant Proposal Guide contains instructions and guidelines for individual investigator proposals. The National Science Board approved review criteria from the Grant Proposal Guide are reproduced below and should be addressed in the review of this proposal.

---

### **Review Criteria**

The National Science Board approved revised criteria for evaluating proposals at its meeting on March 28, 1997 (NSB 97-72). All NSF proposals are evaluated through use of the two merit review criteria. In some instances, however, NSF will employ additional criteria as required to highlight the specific objectives of certain programs and activities. For example, proposals for large facility projects also might be subject to special review criteria outlined in the program solicitation.

The two NSB-approved merit review criteria are listed below. The criteria include considerations that help define them. These considerations are suggestions, and not all will apply to any given proposal. While proposers must address both merit review criteria, reviewers will be asked to address only those considerations that are relevant to the proposal being considered and for which he/she is qualified to make judgments.

#### **What is the intellectual merit of the proposed activity?**

How important is the proposed activity to advancing knowledge and understanding within its own field or across different fields? How well qualified is the proposer (individual or team) to conduct the project? (If appropriate, the reviewer will comment on the quality of prior work.) To what extent does the proposed activity suggest and explore creative and original concepts? How well conceived and organized is the proposed activity? Is there sufficient access to resources?

#### **What are the broader impacts of the proposed activity?**

How well does the activity advance discovery and understanding while promoting teaching, training, and learning? How well does the proposed activity broaden the participation of underrepresented groups (e.g., gender, ethnicity, disability, geographic, etc.)? To what extent will it enhance the infrastructure for research and education, such as facilities, instrumentation, networks, and partnerships? Will the results be disseminated broadly to enhance scientific and technological understanding? What may be the benefits of the proposed activity to society?

NSF staff will give careful consideration to the following in making funding decisions:

### **Integration of Research and Education**

One of the principal strategies in support of NSF's goals is to foster integration of research and education through the programs, projects and activities it supports at academic and research institutions. These institutions provide abundant opportunities where individuals may concurrently assume responsibilities as researchers, educators, and students, and where all can engage in joint efforts that infuse education with the excitement of discovery and enrich research through the diversity of learning perspectives.

### **Integrating Diversity into NSF Programs, Projects, and Activities**

Broadening opportunities and enabling the participation of all citizens, women and men, underrepresented minorities, and persons with disabilities, are essential to the health and vitality of science and engineering. NSF is committed to this principle of diversity and deems it central to the programs, projects, and activities it considers and supports.

---

## **Specific Charge for Advanced LIGO Review Panel**

The original LIGO proposal called for a staged approach to reach the full sensitivity necessary to detect and analyze gravitational radiation from predicted astronomical sources. The installation of detector system upgrades to make this possible was planned to occur after the initial LIGO observation period of 2003 through 2006. The current proposal represents the technical approach to extend the detector sensitivity by a factor of at least ten over the original LIGO design goal and extend the low frequency response from 40 Hz to 10 Hz. The technical plan to achieve this goal is described in the proposal and supporting documents, along with the cost, schedule, and management structure.

We ask that the Panel review the proposed work in technical detail. In carrying out this task, we ask that the following questions be addressed:

- Is the scientific case for the needed upgrade convincing? Are the scientific requirements achieved in a cost-effective manner?
- Is the specific proposed Advanced Detector upgrade appropriate to accomplish the scientific goals? In particular, is the decision to convert the 2-km Hanford interferometer to a second 4-km interferometer well founded, and will the specific subsystems each meet the required performance specifications?
- Are the requested budget (including contingency) and manpower levels appropriate to carry out the proposed upgrade?
- Are the schedule and milestones achievable with the proposed resources? Does the phasing of the downtime of detectors achieve a proper balance of cost, manpower, and observation time?
- Is the proposed management plan appropriate to oversee the R&D, construction, installation and commissioning of the upgrade?
- Has the issue of cost effectiveness in operating the more complex Advanced LIGO system been addressed?
- Is the proposed education and outreach plan well designed, and are the proposed manpower and funds appropriate to carry it out?



# AGENDA

## Wednesday, 6/11

- 08:00 Panel Executive Session (closed)
- 08:25 Introduction and Reading of Panel Charge
- 08:30 Welcoming remarks Barish
- 08:30 LIGO Overview Sanders
- 09:15 Initial LIGO Commissioning and First Observations Whitcomb
- 10:00 Break
- 10:15 Astrophysics Thorne
- 11:00 Overview of Advanced LIGO Shoemaker
- 12:00 Executive lunch (closed; lunch provided)
- 13:00 Cost, Schedule, Management Sanders
- 13:45 Panel Executive Session (closed)
- 14:30 Breakout Sessions:
1. Laser, Input Optics, Core Optics, Auxiliary Optics  
**351 W. Bridge** [Science Conference Rm]
  2. Suspensions, Seismic Isolation, Systems, Sensing/Control, e2e Modelling  
**39 Bridge Annex** [Engineering Conference Rm]
  3. Astrophysics, Data Analysis Hardware, Data Acquisition  
**621 Millikan** [Millikan Large Rm]
  4. Installation, Facilities, Project Management, Cost/Schedule  
**619 Millikan** [Millikan Small Rm]
  5. International Partners, LSC, Outreach  
**102 E. Bridge**
- 17:00 Panel Executive Session (closed).  
Discussion of issues to be revisited in next set of breakout sessions and assignments to breakout sessions
- 18:30 Lab Tour (optional, per committee preference)
- 19:30 Dinner: Holly Street Cafe

## Thursday, 6/12

- 08:30 Panel Executive Session [Review requests for information] (closed)
- 09:00 Response of LIGO/LSC staff to Panel Request and/or Parallel Sessions
- 10:30 Break
- 11:15 Response of LIGO/LSC Staff to Panel Request and/or Parallel Sessions
- 12:30 Lunch and Panel Executive Session (closed)
- 13:30 Executive Session (closed), Interaction with LIGO/LSC staff as desired

## Friday, 6/13

- 09:00 Panel Executive Session [Final discussion of report and closeout presentation] (closed)
- 10:00 Closeout
- 12:00 Adjourn





## Acronyms and Abbreviations

### Acronym

ACIGA	Australian Consortium for Interferometric Gravitational Astronomy
ACWP	Actual Cost of Work Performed
ADC	Analog-to-Digital Converter
AMU	Atomic Mass Unit
ANU	Australian National University
API	Application Programmer Interface
AR	Anti-Reflective
BAC	Budget at Completion
BCWP	Budgeted Cost of Work Performed
BCWS	Budgeted Cost of Work Scheduled
BH	Black Hole
BSC	Basic Symmetric Chamber
BSC	Beam Splitter Chamber
CACR	Center for Advanced Computer Research (Caltech)
CAD	Computer-Assisted Design
CB&I	Chicago Bridge & Iron
CDS	Control and Data System
COBE	Cosmic Background Explorer
CSIRO	Commonwealth Scientific and Industrial Research Organization (Australia)
CSSR	Cost Schedule Status Report
DAC	Data Analysis and Computing
DAC	Digital-to-Analog Converter
DcAPI	Data Conditioning Application Programmer Interface
DMRO	Differential Mode Read-Out
DOF	Degrees of Freedom
EAC	Estimate at Completion
EPI	External Pre-Isolation
EPICS	Experimental Physics and Industrial Control System
ER	LIGO Engineering Run
ETF	Engineering Test Facility
ETM	End Test Mass
FDR	Final Design Review
FFT	Fast (Discrete) Fourier Transform
FTE	Full Time Equivalent
GASF	Geometrical Anti-Spring Filter
GEO	British-German Cooperation for Gravity Wave Experiment
GFLOPS	1000 MFLOPS
GRB	Gamma-Ray Burst
GW	Gravitational Wave
GWADW	Gravitational Wave Data Analysis Workshop
GWIC	Gravitational Wave International Committee
HAM	Horizontal Access Modules
HEPI	Hydraulic External Pre-Isolation

HPSS	High Performance Storage System (IBM)
HVAC	Heating, Ventilation and Air Conditioning
IAP	Institute for Applied Physics
IDE	Integrated Drive Electronics (disk standard)
IFO	Interferometer
IGEC	International Gravitational Event Collaboration
InGaAs	Indium-Gallium-Arsenide
INSA	French National Institute for Applied Science
IO	Input Optics
IP	Inverted Pendulum
ISC	Interferometer Sensing and Control
ISCT	Interferometer Sensing and Control Table
ISS	Intensity Stabilization Servo
ITM	Input Test Mass
ITM-X	X-Arm Input Test Mass
IV&V	Integration, Verification, and Validation
kpc	Kiloparsec
LASTI	LIGO Advanced System Test Interferometer
LDAS	LIGO Data Analysis System
LHO	LIGO Hanford Observatory
LIGO	Laser Interferometer Gravitational-Wave Observatory
LLO	LIGO Livingston Observatory
LMC	Large Magellanic Clouds
LMXB	Low-Mass X-Ray Binary
LSC	LIGO Scientific Collaboration also Length Sensing and Control System
LVDT	Linear Variable Differential Transducer
LVEA	Laser and Vacuum Equipment Area
LZH	Laser Zentrum Hannover
MB	Megabytes
MC	Mode Cleaner
MDC	Mock Data Challenges
MEPI	Electro-Magnetic External Pre-Isolation
MFLOPS	Million Floating Point Operations Per Second
MGASF	Monolithic Geometrical Anti-Spring Filter
MIMO	Multiple Input, Multiple Output
MOPA	Master Oscillator-Power Amplifier
MOU	Memorandum of Understanding
Mpc	Megaparsec
MPI	Message Passing Interface
MSU	Moscow State University
NBI	Neutron Star Binary Inspiral
NCSA	National Center for Supercomputing Applications
NPRO	Non-Planar Ring Oscillator
NS	Neutron Star
OSB	Operations Support Building
OSEM	Optical Shadow Sensor and Magnetic Actuator

<b>PEM</b>	<b>Physics and Environmental Monitor</b>
<b>PM</b>	<b>Project Management</b>
<b>PMP</b>	<b>Project Management Plan</b>
<b>Ppm</b>	<b>Parts per million</b>
<b>PSL</b>	<b>Prestabilized Laser</b>
<b>QND</b>	<b>Quantum Non-Demolition</b>
<b>R&amp;D</b>	<b>Research and Development</b>
<b>RAID</b>	<b>Redundant Array of Inexpensive Disks</b>
<b>REO</b>	<b>Research Electro-Optics (Company Name)</b>
<b>REU</b>	<b>Research Experience for Undergraduates</b>
<b>RF</b>	<b>Radio Frequency</b>
<b>RFP</b>	<b>Request for Proposal</b>
<b>RM</b>	<b>Recycling Mirror</b>
<b>RMS</b>	<b>Root mean square</b>
<b>ROC</b>	<b>Radius of Curvature</b>
<b>RSE</b>	<b>Resonant Sideband Extraction</b>
<b>s</b>	<b>Second</b>
<b>s/s</b>	<b>Samples/second</b>
<b>SAS</b>	<b>Seismic Attenuation System</b>
<b>SEI</b>	<b>Seismic Isolation</b>
<b>SEM</b>	<b>Secondary Emission Monitor</b>
<b>SIOM</b>	<b>Shanghai Institute of Optical Materials</b>
<b>SMC</b>	<b>Small Magellanic Clouds</b>
<b>SNR</b>	<b>Signal to Noise Ratio</b>
<b>SOS</b>	<b>Small Optics Suspensions</b>
<b>SRD</b>	<b>Science Requirements Document</b>
<b>SUBR</b>	<b>Southern Louisiana University at Baton Rouge</b>
<b>SURF</b>	<b>Summer Undergraduate Research Fellowship</b>
<b>TAMA</b>	<b>Japanese Interferometric Gravitational-Wave Project</b>
<b>TB</b>	<b>Terabytes</b>
<b>TES</b>	<b>Technical and Engineering Support</b>
<b>TNI</b>	<b>Thermal Noise Interferometer</b>
<b>TRW</b>	<b>Company Name</b>
<b>UHV</b>	<b>Ultra high vacuum</b>
<b>VME</b>	<b>Versa Modular Eurocard (IEEE 1014)</b>
<b>WAN</b>	<b>Wide Area Network</b>
<b>WBS</b>	<b>Work Breakdown Structure</b>
<b>WFS</b>	<b>Wave Front Sensor</b>
<b>WMAP</b>	<b>Wilkinson Microwave Anisotropy Probe</b>





---

# LIGO Overview

Gary H Sanders  
NSF Review of Advanced LIGO  
Caltech, June 11, 2003



# This talk

---

- Introduction to LIGO and terrestrial gravitational wave detectors
- The LIGO mission and the upgrade strategy
- The scientific reach and impact of Advanced LIGO
- How we are organized for Advanced LIGO
- Broader impacts



# Advanced LIGO In Context

---


- LIGO construction is complete
  - » NSF investment in LIGO now totals about \$400 million
  - » Construction cost \$292 million
  - » LIGO facilities represent ~ 2/3 of the construction investment and are intended to support successive detectors
- Initial LIGO detectors are operating and have carried out early scientific running
  - » Initial LIGO should accomplish its sensitive observation goal by late 2006
- Advanced LIGO development is defining the detailed design and retiring risks
- The experienced LIGO team will be ready to install Advanced LIGO in 2007
- Observations for probable gravitational wave detection can commence in 2010





# LIGO Overview

---





*"Colliding Black Holes"*

Credit:  
National Center for Supercomputing Applications (NCSA)



# Gravity as a “Strain” of Flat Space-Time




*gravitational radiation from  
binary inspiral of compact objects*



# Evidence for Gravitational Waves

## Neutron Binary System – Hulse & Taylor

PSR 1913 + 16 -- Timing of pulsars



### Neutron Binary System


- separated by  $10^6$  miles
- $m_1 = 1.4m_{\odot}$ ;  $m_2 = 1.36m_{\odot}$ ;  $\varepsilon = 0.617$

### Prediction from general relativity

- spiral in by 3 mm/orbit
- rate of change orbital period


## Emission of gravitational waves

Comparison between observations of the binary pulsar PSR1913+16, and the prediction of general relativity based on loss of orbital energy via gravitational waves



From J. H. Taylor and J. M. Weisberg, unpublished (2000)


# Direct Detection



Gravitational Wave  
Astrophysical Source

Terrestrial detectors  
**LIGO, GEO, TAMA, Virgo**


Detectors  
in space  
**LISA**






# Astrophysics Sources by Frequency

- EM waves are studied over ~20 orders of magnitude  
» (ULF radio → HE  $\gamma$ -rays)
- Gravitational Waves over ~10 orders of magnitude  
» (terrestrial + space)





# A New Window on the Universe



**Gravitational Waves will provide a new way to view the dynamics of the Universe**




# Astrophysical Sources of Gravitational Waves

## Compact binary inspiral:

- » NS-NS waveforms are well described
- » BH-BH need better waveforms
- » search technique: matched templates

*“chirps”*




Thorne

## Supernovae / GRBs:


- » burst signals in coincidence with signals in electromagnetic radiation
- » Challenge to search for untriggered bursts

*“bursts”*




## Pulsars in our galaxy: *“periodic signals”*

- » search for observed neutron stars (frequency, doppler shift)
- » all sky search (computing challenge)
- » r-modes




## Cosmological Signals *“stochastic background”*



# Detecting a passing wave ....

---

Free masses






# Detecting a passing wave ....

---

Interferometer



# Interferometer Concept


- Laser used to measure relative lengths of two orthogonal arms

- Arms in LIGO are 4km
- Measure *difference in length to one part in  $10^{21}$  or  $10^{-18}$  meters*



...causing the interference pattern to change at the photodiode

As a wave passes, the arm lengths change in different ways....






# An International Network of Interferometers

Hough, Wilke

Simultaneously detect signal (within msec)




detection confidence

locate the sources

decompose the polarization of gravitational waves



# LIGO Organization & Support






# The Laboratory Sites

## Laser Interferometer Gravitational-wave Observatory (LIGO)

Hanford  
Observatory



Livingston  
Observatory




# LIGO Livingston Observatory






# LIGO Hanford Observatory

---





# GEO 600



Hough, Wilke



# LIGO Beam Tube



1.2 m diameter - 3mm stainless  
50 km of weld

**NO LEAKS !!**

- LIGO beam tube under construction in January 1998
- 65 ft spiral welded sections
- girth welded in portable clean room in the field



# LIGO Vacuum Equipment

---



LIGO-G030250-01-M

*LIGO Laboratory*

21



# A LIGO Mirror

## Substrates: $\text{SiO}_2$

25 cm Diameter, 10 cm thick

Homogeneity  $< 5 \times 10^{-7}$

Internal mode Q's  $> 2 \times 10^6$

## Polishing

Surface uniformity  $< 1 \text{ nm rms}$


Radii of curvature matched  $< 3\%$

## Coating

Scatter  $< 50 \text{ ppm}$


Absorption  $< 0.5 \text{ ppm}$

Uniformity  $< 10^{-3}$



# Core Optics

## *installation and alignment*




LIGO team now expert in this very demanding work



# What Limits Sensitivity of Interferometers?


- Seismic noise & vibration limit at low frequencies
- Atomic vibrations (Thermal Noise) inside components limit at mid frequencies
- Quantum nature of light (Shot Noise) limits at high frequencies
- Myriad details of the lasers, electronics, etc., can make problems above these levels

Running at  $10^{-7}$






# LIGO Sensitivity Livingston 4km Interferometer





# LIGO Commissioning and the First Science Runs





# LIGO Plans *schedule*


---

1996	Construction Underway (mostly civil)
1997	Facility Construction (vacuum system)
1998	Interferometer Construction (complete facilities)
1999	Construction Complete (interferometers in vacuum)
2000	Detector Installation (commissioning subsystems)
2001	Commission Interferometers (first coincidences)
 2002	Sensitivity studies (initiate LIGO I Science Run)
 2003+	LIGO I data run (one year integrated data at $h \sim 10^{-21}$ )
2007	Begin 'advanced' LIGO installation





# Advanced LIGO Reach



*Science from a few hours of Advanced LIGO observing should be comparable to 1 year of initial LIGO!*



# Historical Background

---

- LIGO was approved for construction of
  - » a platform suitable for successive and additional interferometers
  - » an initial set of interferometers
- 1996 McDaniel report endorsed plans for:
  - » NSF support of an Advanced R&D program to lead to the detectors beyond initial LIGO
  - » formation of a scientific collaboration
    - LIGO Scientific Collaboration (LSC)
- R&D proposals from LIGO Lab and LSC received late 1996
  - » NSF defined a budget and program in 1998
  - » R&D was organized and initiated in 1997 – 2001 period



# Establishing a Supported Development Program

---

- LSC authored a White Paper on an advanced LIGO detector in 1998 and described a reference concept and R&D program
  - » This was an international R&D program from the start
- LIGO Lab and LSC jointly submitted a revised White Paper and a project conceptual document to NSF in late 1999
  - » Proposed upgrade of 3 interferometers, all 4 km arms, simultaneous installation
  - » Peoples panel endorsed concept and urged support of the development program
  - » NSF decided to support further R&D for Advanced LIGO development



# The Current LIGO Laboratory Development Program

---

- In 2000, LIGO Lab proposed to NSF continuation of LIGO operations and R&D for the period FY2002 – FY2006
  - » Program and budget included support of
    - Operating initial LIGO
    - Analyzing data and producing science
    - Developing Advanced LIGO through Final Design
  - » Permanent LIGO staff scientists and engineers engaged in Advanced LIGO development were to be supported from the basic operating budget
  - » Equipment, fabrications, incremental labor were to be supported from an Advanced R&D budget line



# Proposal Budget

## LIGO Operations (2002 – 2006)

	FY 2001 (\$M)	FY 2002 (\$M)	FY 2003 (\$M)	FY 2004 (\$M)	FY 2005 (\$M)	FY 2006 (\$M)	Total 2002-6 (\$M)
Currently funded Operations	22.92	23.63	24.32	25.05	25.87	26.65	125.52
Increase for Full Operations		5.21	5.20	4.79	4.86	4.95	25.01
Advanced R&D	2.70	2.77	2.86	2.95	3.04	3.13	14.76
R&D Equipment for LSC Research		3.30	3.84	3.14			10.28
<b>Total Budgets</b>	<b>25.62</b>	<b>34.91</b>	<b>36.21</b>	<b>35.93</b>	<b>33.77</b>	<b>34.74</b>	<b>175.57</b>

FY 2001 currently funded Operations (\$19.1M for ten months) is normalized to 12 months and provided for comparison only and is not included in totals.



# “Revised” Proposal Budget LIGO Operations (2002-2006)

- \$28 million provided for FY 2002 Operations in February and May 2002
  - » Reduced or deferred hiring, Adv R&D, equipment, outreach, etc
- Priority for commissioning and toward LIGO 24x7 Operations
- Full \$33 million awarded for FY2003 (6 months late)

	FY 2002 (\$M)	FY 2003 (\$M)	FY 2004 (\$M)	FY 2005 (\$M)	FY 2006 (\$M)
Operations	\$24	\$29	\$30	\$30	\$30
Advanced R&D	\$4	\$4	\$3	\$3	\$3





# Funding for LIGO Laboratory Program

---

- NSF award for continuing LIGO operations is at a level less than requested
- FY2003 appropriations delayed 6 months
- Initial LIGO operations and data analysis/science is highest priority
- Nevertheless, the Advanced LIGO development program has accomplished much of what was proposed
  - » The LSC has been a full partner in all of these activities
  - » Advanced LIGO R&D not run as a firm project though we are ready



# A Development Project Across the LSC

---

Since late 1999, we have planned the Advanced LIGO development program as if it was part of a construction project

- » Work Breakdown Structure
- » Cost estimate
- » Schedule
- » Management structure
- » Requirements documented and systems engineering and modeling
- » Design process established

This “projectized” development program has been operating in a serious collaborative manner across the LSC

- » LSC Working Groups
  - Advanced detector configurations working group
  - Core optics working group
  - Laser working group
  - Suspensions working group





# Advanced LIGO Proposal

---

- R&D through final design and full prototypes now underway
  - » supported by LIGO and partner funds already awarded
  - » a true LSC-wide activity
- Proposal requests funding for the construction
  - » \$123 million beginning in 2005
  - » Some early purchases in 2004
- International partners propose support of additional \$25.5 million
  - » GEO (UK) - \$11.5 million (**approved**) Hough, Willke
  - » GEO (Germany) - \$11.5 million
  - » ACIGA - \$2.5 million McClelland



# What are we proposing?

---

- Replace all three interferometers
  - » Provides **sensitive** suite of detectors during “discovery” phase
  - » Versatile and robust during post-detection exploration
- Convert current 2 km interferometer in Hanford to a 4 km interferometer
  - » Emphasis placed upon **sensitivity**
  - » Cost is a fraction of one percent of the project

Shoemaker



# Phasing of Interferometer Replacements

- Initial LIGO installation and commissioning taught us many lessons
  - » How to effectively use expert teams
  - » How to properly phase rework and installation
  - » How to interleave installation with early commissioning
  - » How to transfer lessons from one interferometer to the others
  - » **Properly phasing the work on the three interferometers can optimize the progress**
  - » **Complete R&D before final installation**
- Minimizing scientific “down time” is a major goal of the LSC
  - » How we accomplish this should be coordinated with the international network of detectors through the Gravitational Wave International Committee
- Installation into LIGO vacuum system should take place after prototype program retires most risk
  - » R&D program tests advanced prototypes fully



# Phasing Implementation of the 3 Interferometers

---

- Replacing all 3 interferometers simultaneously
  - » minimizes duration of LIGO down time
  - » very expensive in expert staffing and resulting rework
- Strict serial replacement of 3 interferometers
  - » reduces duplication of skilled teams and tooling
  - » maintains at least one interferometer operating as much as possible
  - » stretches out period before the upgraded set of detectors is available
- Rapid and overlapping phasing of replacement/upgrade ✓
  - » Balances application of skilled teams and resources with scientific imperative to bring set of detectors on line
- International community and scientific review will enable us to further optimize this balance



# Buildup of Education and Outreach

---

- LIGO Lab outreach has been primarily observatory centered
- LIGO Lab renewal called for increased activity
- Supported new effort and formed a strategy and Local Educator's Networks at each observatory
- This process led to a new proposal with partners for a greatly expanded program
  - » Next slide has some details
- NSF is beginning an effort to produce a “half-hour” video on LIGO
- **Advanced LIGO proposal calls for an LSC-wide education and outreach program**



# LSC Outreach Program Startup

---

- FY2004 – Recruit LSC Outreach Director and assistant
- FY2004 – Survey all LSC education and outreach activities and develop a descriptive survey document
- FY2004 – Formation of LSC Educators Advisory Network
- FY2004 – August 2004 LSC meeting hosts an additional two day LSC Outreach Workshop at which all LSC activities are showcased and attendees, including outside consultants and advisory network members participate in design discussions for an enhanced, coordinated LSC program
- FY2005 – LSC Outreach Director develops detailed program plan with review meetings and educators advisory network participation
- FY2005 – March 2005 LSC meeting hosts one day LSC Outreach Workshop to finalize and approve program plan
- FY2005 – Initial elements of the plan implemented
- FY2005 – Supplemental proposals to NSF are submitted as necessary
- FY2006 – Initial operation of the coordinated LSC outreach programs



# February 2003 Proposed Education & Outreach Program

---

Proposal submitted to NSF Feb. 10 for major enhancement to outreach activity:

» Collaboration of Caltech, SUBR, La Board of Regents, Exploratorium of San Francisco

Construct an educational outreach center on-site at LLO.

Place hands-on exhibits from Exploratorium in center (with subset at LHO).

Implement teacher pre-service and in-service training initiative to teach inquiry based science techniques at SUBR – extend to LHO communities

Use LIGO staff to provide science leadership in selection of exhibits, development of science content in teacher training programs

La Board of Regents, through La Systemic Initiative with leveraged resources from US Dept of Education LA GEAR UP program, will facilitate teacher training and student visits to outreach center from underserved communities.



# Advanced LIGO In Context

---

- LIGO construction is complete
  - » NSF investment in LIGO now totals about \$400 million
  - » Construction cost \$292 million
  - » LIGO facilities represent ~ 2/3 of the construction investment and are intended to support successive detectors
- Initial LIGO detectors are operating and have carried out early scientific running
  - » Initial LIGO should accomplish its sensitive observation by late 2006
- Advanced LIGO development is defining the detailed design and retiring risks
- The experienced LIGO team will be ready to install Advanced LIGO in 2007
- Observations for probable gravitational wave detection can commence in 2010





# Mission and Strategy

---

- Observe gravitational waves directly
- Initiate gravitational wave astronomy
- Bring initial LIGO to design sensitivity and observe for one integrated year at that sensitivity
  - » “plausible” chance to detect gravitational waves
- Upgrade detector with a very significant increment in sensitivity
  - » “probable” detection of gravitational waves



# Plenary Talks

---

- LIGO Overview – Sanders
- LIGO Commissioning and First Results – Whitcomb
- Astrophysics – Thorne
- Advanced LIGO – Shoemaker
- Cost, Schedule and Management - Sanders



# Specific Charge

---


- 1. Is the scientific case for the needed upgrade convincing? Are the scientific requirements achieved in a cost-effective manner?
- 2. Is the specific proposed Advanced Detector upgrade appropriate to accomplish the scientific goals? In particular, is the decision to convert the 2-km Hanford interferometer to a second 4-km interferometer well founded, and will the specific subsystems each meet the required performance specifications?
- 3. Are the requested budget (including contingency) and manpower levels appropriate to carry out the proposed upgrade?
- 4. Are the schedule and milestones achievable with the proposed resources? Does the phasing of the downtime of detectors achieve a proper balance of cost, manpower, and observation time?
- 5. Is the proposed management plan appropriate to oversee the R&D, construction, installation and commissioning of the upgrade?
- 6. Has the issue of cost effectiveness in operating the more complex Advanced LIGO system been addressed?
- 7. Is the proposed education and outreach plan well designed, and are the proposed manpower and funds appropriate to carry it out?





---

## *Initial LIGO Commissioning and First Observations*



*Stan Whitcomb*


NSF AdvLIGO Review

Caltech

11 June 2003




# Commissioning History



# Strain Sensitivity for the LLO 4km Interferometer

31 January 2003

LIGO-G030014-00-E






# First Science Run (S1)

- August 23 - September 9 (~400 hours)
- Three LIGO interferometers, plus GEO (Europe) and TAMA (Japan)
- Hardware reliability good for this stage in the commissioning
  - » Longest locked section for individual interferometer: 21 hrs

Strain Sensitivities for the LIGO Interferometers for S1  
23 August 2002 - 09 September 2002 LIGO-G020461-00-E




	LLO-4K	LHO-4K	LHO-2K	3x Coinc.
Duty cycle	42%	58%	73%	24%






# Astrophysical Searches with S1 Data

- Compact binary inspiral: *“chirps”*
  - » NS-NS waveforms are well described
  - » BH-BH need better waveforms
  - » search technique: matched templates




- Supernovae / GRBs: *“bursts”*
  - » burst signals in coincidence with signals in electromagnetic
  - » prompt alarm


Four papers describing results in final stages of preparation




- Pulsars in our galaxy: *“bursts”*
  - » search for observed neutron stars (frequency, doppler shift)
  - » all sky search (computing challenge)
  - » r-modes



- Cosmological Signals: *“stochastic background”*



# Compact Binary Coalescence




» Search: matched templates

» Neutron Star – Neutron Star  
– waveforms are well described


» Black Hole – Black Hole  
– need better waveforms

- Discrete set of templates labeled by  $(m_1, m_2)$ 
  - »  $1.0 \text{ Msun} < m_1, m_2 < 3.0 \text{ Msun}$
  - » 2110 templates
  - » At most 3% loss in SNR





# Results of S1 Inspiral Search



## Simulated Galactic Population

- Population includes Milky Way, LMC and SMC
- LMC and SMC contribute ~12% of Milky Way

**LIGO S1 Upper Limit**  
 **$R < 160 / \text{yr} / \text{MWEG}$**

» Japanese TAMA →  $R < 30,000 / \text{yr} / \text{MWEG}$

» Caltech 40m →  $R < 4,000 / \text{yr} / \text{MWEG}$

• Theoretical prediction  $R < 2 \times 10^{-5} / \text{yr} / \text{MWEG}$

**Detectable Range for S2 data will reach Andromeda!**


- **Known sources -- Supernovae & GRBs**

- » **Coincidence with observed electromagnetic observations.**

- » **No close supernovae occurred during the first science run**


- » **Second science run – We are analyzing the recent very bright and close GRB030329**

**NO RESULT YET**



- **Unknown phenomena**



- » **Emission of short transients of gravitational radiation of unknown waveform (e.g. black hole mergers).**



# 'Unmodelled' Burst Search

**GOAL** search for waveforms from sources for which we cannot currently make an accurate prediction of the waveform shape.

**METHODS** 'Raw Data' → Time-domain high pass filter






# Determination of Efficiency


Detector efficiency vs amplitude, average over sources. GA  $\tau=1.0\text{ms}$

To measure our efficiency, we must pick a waveform.

1ms Gaussian burst



Efficiency measured for 'tfclusters' algorithm






# Upper Limit

## 1ms gaussian bursts


Result is derived using 'TFCLUSTERS' algorithm



Upper limit in strain compared to earlier (cryogenic bar) results:

- IGEC 2001 combined bar upper limit:  $< 2$  events per day having  $h=1 \times 10^{-20}$  per Hz of burst bandwidth. For a 1kHz bandwidth, limit is  $< 2$  events/day at  $h=1 \times 10^{-17}$
- Astone *et al.* (2002), report a one sigma excess of one event per day at strain level of  $h \sim 2 \times 10^{-18}$

- Pulsars in our galaxy:
  - » search for observed neutron stars
  - » all sky search (computing challenge)
  - » r-modes




- Frequency modulation of signal due to Earth's motion
- Amplitude modulation due to the detector's antenna pattern.





# Directed Search in S1

NO DETECTION EXPECTED  
at present sensitivities



Predicted signal for rotating neutron star with equatorial ellipticity  $\epsilon = \delta I/I : 10^{-3}, 10^{-4}, 10^{-5}$  @ 8.5 kpc.

PSR J1939+2134  
1283.86 Hz



## Two Search Methods

---

### Frequency domain

- Best suited for large parameter space searches
- Maximum likelihood detection method + frequentist approach

### Time domain

- Best suited to target known objects, even if phase evolution is complicated
- Bayesian approach

**First science run --- use both pipelines for the same search for cross-checking and validation**



## Results: PSR J1939+2134

- No evidence of continuous wave emission from PSR J1939+2134.
- Summary of 95% upper limits on  $h$ :


<b>IFO</b>	<b>Frequentist FDS</b>	<b>Bayesian TDS</b>
<b>GEO</b>	$(1.94 \pm 0.12) \times 10^{-21}$	$(2.1 \pm 0.1) \times 10^{-21}$
<b>LLO</b>	$(2.83 \pm 0.31) \times 10^{-22}$	$(1.4 \pm 0.1) \times 10^{-22}$
<b>LHO-2K</b>	$(4.71 \pm 0.50) \times 10^{-22}$	$(2.2 \pm 0.2) \times 10^{-22}$
<b>LHO-4K</b>	$(6.42 \pm 0.72) \times 10^{-22}$	$(2.7 \pm 0.3) \times 10^{-22}$

- Best previous results for PSR J1939+2134:  
 $h_o < 10^{-20}$  (Glasgow, Hough et al., 1983)




# Early Universe *stochastic background*


## 'Murmurs' from the Big Bang



**Cosmic Microwave background**



**WMAP 2003**







# Stochastic Background

- Strength specified by *ratio of energy density in GWs to total energy density* needed to close the universe:

$$\Omega_{GW}(f) = \frac{1}{\rho_{critical}} \frac{d\rho_{GW}}{d(\ln f)}$$

- Detect by *cross-correlating* output of two GW detectors:






## Preliminary Limits: Stochastic Search

Interferometer Pair	90% CL Upper Limit	$T_{\text{obs}}$
LHO 4km-LLO 4km	$\Omega_{\text{GW}}(40\text{Hz} - 314 \text{ Hz}) < 72.4$	62.3 hrs
LHO 2km-LLO 4km	$\Omega_{\text{GW}}(40\text{Hz} - 314 \text{ Hz}) < 23$	61.0 hrs


- Non-negligible LHO 4km-2km (H1-H2) instrumental cross-correlation; currently being investigated.
- Previous best upper limits:
  - » *Measured*: Garching-Glasgow interferometers :  $\Omega_{\text{GW}}(f) < 3 \times 10^5$
  - » *Measured*: EXPLORER-NAUTILUS (cryogenic bars):  $\Omega_{\text{GW}}(907\text{Hz}) < 60$



# Stochastic Background sensitivities and theory




# S1 Noise Component Analysis, LLO 4k






## Estimated Noise Limits for S2 (as planned in October 2002)



# Strain Sensitivity for the LLO 4km Interferometer

31 January 2003

LIGO-G030014-00-E





## *Changes Between S1 and S2*

---

- Digital Suspensions installed on LHO-2K and LLO-4K
  - » New coil drivers & realtime control code for suspensions
  - » Lower noise, switchable dynamic range (200 mA acquisition, 5 mA running)
  - » Separate DC biases for alignment
  - » Better filtering, diagonalization and control/sequencing features
- Optical lever improvements
  - » Structural stiffening (designed for thermal/kinematic stability, not low vibration)
  - » Improved filtering to take advantage of reduced resonances
  - » Pre-ADC "whitening" for improved dynamic reserve
- More Power
  - » Enabled by better alignment stability
  - » Also required control of "I-phase" photocurrent (overload)
  - » Now ~ 1.5 W into mode cleaners, ~ 40 W at beamsplitter ( $R \sim 40$ )
  - » Only 10-20 mA average DC photocurrent at dark ports !! (optics very good)



## Second Science Run (S2)

- February 14 – April 14, 2002 (~ 1400 hours)
- Three LIGO interferometers and TAMA (Japan)
- Steady improvement in sensitivity continues
  - » Approximately 10x improvement over S1
- Duty cycle similar to S1
  - » Increased sensitivity did not degrade operation
  - » Longest locked stretch ~ 66 hours (LHO-4K)

	LLO-4K	LHO-4K	LHO-2K	3x Coinc.
Duty cycle (cf. S1)	37% (42%)	74% (58%)	58% (73%)	22% (24%)



## *Stability improvements for S2*


---

- Wavefront sensing (WFS) for alignment control
  - » Uses the main laser beam to sense the proper alignment for the suspended optics
  - » Complex! 10 coupled degrees of freedom,
    - Sensing degrees-of-freedom different from control degrees-of-freedom
- S1:
  - » All interferometers had 2 degrees-of-freedom controlled by WFS
- S2:
  - » LHO-4K: 8 of 10 alignment degrees-of-freedom under feedback control
- Now:
  - » All 10 degrees-of-freedom controlled by WFS



Virgo Cluster

# S2 Sensitivity and Stability





## *Major On-going Commissioning Activities*

---

- Seismic retrofit at LLO
- Finish wavefront sensing alignment system
- RFI cleanup, linear power supplies
- Shot noise sensitivity
  - » Thermal lensing
  - » Increase of number of photodiodes
- Acoustic coupling
- Numerous smaller tasks




## *Seismic Isolation Upgrade*

---

- The Seismic Isolation System at LLO needs to be upgraded
  - » Seismic noise environment much worse below 10 Hz than originally planned (logging largest factor, but also train, other anthropogenic noise)
  - » Plan is to add an active, external pre-isolation (EPI) stage without disturbing the alignment of the installed optics
- Current Plan:
  - » Continue prototype testing at MIT, including testing VME based controls
  - » Review held for 4/18; management decision on how to proceed pending
  - » Order components, fabricate and assemble; fabrication/assembly phase lasts ~5.5 months
  - » Installation starts ~Jan '04 and should complete ~Apr '04




## Hydraulic External Pre-Isolator (HEPI)




LIGO-G030280-00-D

## electro-Magnetic External Pre-Isolator (MEPI)



AdvLIGO Review -- June 2003

- Simplistic power calculations suggests factor of  $\sim 2$  shortfall
  - » 10x increase in laser power would give factor  $\sim 3$  improvement
- Does not take improved sideband efficiency into account






## Optical characterization


- Good news: optics quality is (almost all) good
  - » Recycling gain meets or exceeds goals (design was >30)
    - LLO-4K: Gain of nearly 50 seen, more usually about 45
    - LHO-4K : Gain of 40-45
  - » Contrast defect meets or exceeds goals (design was < 10<sup>-3</sup>)
    - LLO-4K :  $P_{as}/P_{bs} = 3 \times 10^{-5}$
    - LHO-4K :  $P_{as}/P_{bs} = 6 \times 10^{-4}$
  - » LHO-2K: Cause of low recycling gain (20) discovered
    - Bad AR coating on ITMX, ~~must be replaced~~  
has been
- Low RF sideband gain/efficiency
  - » LHO-4K : Sideband power efficiency to AS port: ~6%
  - » Cause: thermal lensing in the ITMs isn't at the design level
  - » Achieving shot noise goal requires that this be fixed

- RF sideband efficiency is low
  - » Power recycling cavity slightly unstable: lack of Input Test Mass (ITM) thermal lens makes  $g_1 \cdot g_2 > 1$
  - » Recycling Mirror (RM) curvature relies on point design for thermal lensing
  - » Heating differs from design value
- Possible solutions
  - » Change RM (w/ new radius of curvature); 6 month lead time
  - » Add the missing heat to ITMs with another source (AdvLIGO or GEO technique)
  - » Pursued in parallel with other commissioning activities



**ITM Heating**

**Bad mode overlap**




**DC (carrier)**

**RF sidebands**



## Acoustic Peaks: Scattering/clipping

- Peaks occur in 80-1000 Hz band, at 10-100x required level
- Source for LHO correlated noise (stochastic search)
- Investigating:
  - » Acoustic isolation improvements
  - » Modify output periscopes/mirror mounts: stiffer, damped
  - » Active beam direction stabilization
  - » Eliminate electro-optic shutters



- Commissioning of detectors progressing well
  - » Steady progression on all fronts: sensitivity, duty cycle, stability, ...
  - » Next Science Run: Nov 2003 – Jan 2004
- First Science analyses underway
  - » S1 results demonstrate analysis techniques, S2 data (and beyond) offer a real possibility to detect gravitational waves
  - » Developing synergy between detector commissioning and data analysis efforts
  - » Four analysis papers (and one instrumental one...) in final stages of preparation
- Design performance (both sensitivity and duty cycle) should be achieved next year
  - » **Still a lot to do, but no showstoppers**





---

# ASTROPHYSICS

Kip S. Thorne

CaRT, California Institute of Technology

*NSF Advanced LIGO Review*


*Pasadena, 11 June 2003*





# From Initial Interferometers to Advanced


$$h_{\text{rms}} = h(f) \sqrt{f} \sim 10 h(f)$$





# Conventions on Source/Sensitivity Plots

- Assume the best search algorithm now known
- Set Threshold so false alarm probability = 1%
  - » For rare broadband signals: on tail of Gaussian; increase S/T by ~10% → 0.01% false alarm



# Overview of Sources

- **Neutron Star & Black Hole Binaries**

- » inspiral
- » merger

- **Spinning NS's**


- » LMXBs
- » known pulsars
- » previously unknown

- **NS Birth (SN, AIC)**

- » tumbling
- » convection


- **Stochastic background**

- » big bang
- » early universe





# Neutron Star / Neutron Star Inspiral (our most reliably understood source)



**1.4 Msun / 1.4 Msun  
NS/NS Binaries**

## Event rates


- » V. Kalogera, R. Narayan, D. Spergel, J.H. Taylor  
*Astrophys J*, 556, 340 (2001)

## Initial IFOs

- » Range: 20 Mpc
- » 1 / 3000 yrs to 1 / 4yrs


## Advanced IFOs -

- » Range: 350Mpc
- » 2 / yr to 3 / day






# Science From Observed Inspirals: NS/NS, NS/BH, BH/BH



- Relativistic effects are very strong -- e.g.
  - » *Frame dragging by spins → precession → modulation*
  - » *Tails of waves modify the inspiral rate*




- Information carried:
  - » *Masses (a few %), Spins (?few%?), Distance [not redshift!] (~10%), Location on sky (~1 degree)*

$$- M_{\text{chirp}} = \mu^{3/5} M^{2/5} \text{ to } \sim 10^{-3}$$

- Search for EM counterpart, e.g.  $\gamma$ -burst. If found:
  - » *Learn the nature of the trigger for that  $\gamma$ -burst*
  - » *deduce relative speed of light and gw's to  $\sim 1 \text{ sec} / 3 \times 10^9 \text{ yrs} \sim 10^{-17}$*



# Neutron Star / Black Hole Inspiral and NS Tidal Disruption



**1.4Msun / 10 Msun  
NS/BH Binaries**

## Event rates


- » Population Synthesis [Kalogera's summary]

## Initial IFOs

- » Range: 43 Mpc
- » 1 / 5000 yrs to 1 / 3yrs

## Advanced IFOs

- » Range: 750 Mpc
- » 1 / yr to 4 / day





# Black Hole / Black Hole Inspiral and Merger

## 10Msun / 10 Msun BH/BH Binaries

### Event rates


- » Population synthesis [Kalogera's summary]

### Initial IFOs

- » Range: 100 Mpc
- » ~1 / 250 yrs to ~2 / yr


### Advanced IFOs -

- » Range:  $z=0.45$  [1.7 Gpc]
- » ~1 / month to ~1 / hour





# BH/BH Mergers: Exploring the Dynamics of Spacetime Warpage



**To interpret  
Observed waves:  
Compare with  
Numerical  
Relativity  
Simulations**






# Probing Intermediate Mass BH's with Small BH's

In globular clusters: BH-BH capture formation, merger,  
formation, merger, ... in globular clusters → intermediate-  
mass BH: 100 - 1000 Msun [Cole Miller]


Plunge of few Msun BH into few ~100 Msun BH

Ringdown studies:  
~ 10 per year with  
 $M/m > 60$ ; more for  
smaller  $M/m$





# Massive BH/BH Mergers with Fast Spins - Advanced IFOs






# Spinning NS's: Pulsars in Our Galaxy

## NS Ellipticity:

- » Crust strength or B strength  
 $\epsilon \lesssim 10^{-5}$

## Known Pulsars:

- » First Interferometers:  
 $\epsilon \gtrsim 3 \times 10^{-6} (1000 \text{ Hz}/f) \times (\text{distance}/10 \text{ kpc})$
- » Broadband Advanced  
 $\epsilon \gtrsim 5 \times 10^{-7} \times (\text{distance}/10 \text{ kpc})$







# Spinning NS's: Pulsars in Our Galaxy [narrow-banded interferometer]

Plausible:  $\epsilon \lesssim 10^{-5}$

Known Pulsars

Unknown: All  
Sky search



Tune by moving Signal Recycling Mirror



# Spinning Neutron Stars: Low-Mass X-Ray Binaries in our Galaxy


Rotation rates  $\sim 250$  to  $\sim 600$   
revolutions / sec

- » Why not faster?
- » **Bildsten**: Spin-up torque balanced by GW emission torque

If so, & steady state: observed  
X-ray flux  $\rightarrow$  GW strength

Combined GW & EM  
obs's  $\rightarrow$  information about:

- » crust strength & structure,  
temperature dependence of  
viscosity, ...





# NS Birth: Tumbling Bar; Convection

## Born in:

- » Supernovae
- » Accretion-Induced Collapse of White Dwarfs



## If very fast spin:

- » Centrifugal hangup
- » **Tumbling bar** - episodic? (for a few sec or min)
- » *If modeling gives enough waveform information, detectable to:*

- Initial IFOs: ~5Mpc (M81 group, ~1 supernova/3yr)
- Advanced IFOs: ~100Mpc (~500 supernovae/yr)

## If slow spin:

- » **Convection** in first ~1 sec.
- » Advanced IFOs: Detectable only in our Galaxy (~1/30yrs)
- » **GW / neutrino correlations!**





# Complementarity of LIGO & LISA

---

## LIGO


- High-frequency band: ~10Hz to ~1500Hz (analog of optical astronomy)
- Neutron-star studies:
  - » Tidal disruption by BH
  - » Low Mass X-Ray Binaries
  - » Pulsar Spins
- Study stellar mass BH's (~3 Msun to ~1000 Msun)
- Study merger of NS and BH binaries in distant galaxies
- Study early universe at age  $\sim 10^{-25}$  sec ( $\sim 10^9$  GeV)

## LISA

- Low-frequency band: ~0.0001 Hz to ~0.1 Hz (analog of radio astronomy)
- Cannot study neutron star physics
- Study supermassive BH's (~100,000 to 10,000,000 Msun)
- Study White dwarf, NS, and BH binaries in our galaxy, long before merger
- Study early universe at age  $\sim 10^{-12}$  sec ( $\sim 100$  GeV)

# Stochastic Background from Very Early Universe

- GW's are the ideal tool for probing the very early universe -- "messenger" from first one second



- **Present limit on GWs**

- » From effect on primordial nucleosynthesis

- »  $\Omega = (\text{GW energy density}) / (\text{closure density}) \lesssim 10^{-5}$





# Stochastic Background from Very Early Universe

- Detect by

- » cross correlating output of Hanford & Livingston 4km IFOs

- Good sensitivity requires


- » (GW wavelength)  $\gtrsim 2x$ (detector separation)
  - »  $f \lesssim 40$  Hz

Initial IFOs detect if

- »  $\Omega \gtrsim 10^{-5}$

Advanced IFOs:


- »  $\Omega \gtrsim 1 \times 10^{-9}$  with reduced power & 3 month search





# Grav'l Waves from Very Early Universe. *Unknown Sources*

- Waves from **standard inflation**:  $\Omega \sim 10^{-15}$ : much too weak
- **BUT**: Crude **superstring models** of big bang suggest waves *might be strong enough* for detection by Advanced IFOs
- Bursts from **cosmic strings**: possibly detectable by Initial IFOs
- Energetic processes at (universe age)  $\sim 10^{-25}$  sec and (universe temperature)  $\sim 10^9$  Gev  $\rightarrow$  GWs in LIGO band
  - » **phase transition at  $10^9$  Gev**
  - » **excitations of our universe as a 3-dimensional “brane” (membrane) in higher dimensions: [C. Hogan]**
    - Brane forms wrinkled
    - When wrinkles “come inside the cosmological horizon”, they start to oscillate; oscillation energy goes into gravitational waves
    - LIGO probes waves from wrinkles of length  $\sim 10^{-10}$  to  $10^{-13}$  mm
    - **If wave energy equilibrates: possibly detectable by initial IFOs**
- Example of hitherto **UNKNOWN SOURCE**





# Conclusions

---

- LIGO's **Initial Interferometers** bring us into the realm where it is plausible to begin detecting cosmic gravitational waves.
- With LIGO's **Advanced Interferometers** we can be confident of:
  - » detecting waves from a variety of sources
  - » gaining major new insights into the universe, and into the nature and dynamics of spacetime curvature, that cannot be obtained in any other way






# Overview of Advanced LIGO

David Shoemaker  
NSF Review of Advanced LIGO  
11 June 2003

- LIGO mission: detect gravitational waves and  
**initiate GW astronomy**
- Next detector
  - » Should have assured detectability of known sources
  - » Should be at the limits of reasonable extrapolations of detector physics and technologies
  - » Must be a realizable, practical, reliable instrument
  - » Should come into existence neither too early nor too late

**→ Advanced LIGO**





# Initial and Advanced LIGO

Factor 10 better amplitude sensitivity

» (Reach)<sup>3</sup> = rate

Factor 4 lower frequency bound

NS Binaries: for three interferometers,


- » Initial LIGO: ~20 Mpc
- » Adv LIGO: ~350 Mpc

BH Binaries:

- » Initial LIGO: 10 M<sub>⊙</sub>, 100 Mpc
- » Adv LIGO : 50 M<sub>⊙</sub>, z=2


Stochastic background:

- » Initial LIGO: ~3e-6
- » Adv LIGO ~3e-9





# Anatomy of the projected Adv LIGO detector performance




- Advanced LIGO's Fabry-Perot Michelson Interferometer is a platform for all currently envisaged enhancements to this detector architecture






# Design features




## Laser



# Pre-stabilized Laser


- Require the maximum power compatible with optical materials
  - » 1999 White Paper: 180 W at output of laser, leads to 830 kW in cavities
  - » Continue with Nd:YAG, 1064 nm
  - » 2002: Three approaches studied by LSC collaboration – stable/unstable slab oscillator (Adelaide), slab amplifier (Stanford), end-pumped rod oscillator (Laser Zentrum Hannover (LZH)); evaluation concludes that all three look feasible
  - » Choose the end-pumped rod oscillator, injection locked to an NPRO ➡
  - » 2003: Prototyping well advanced – 1/2 of Slave system has developed 87 W ➡



# Pre-stabilized laser

Overall subsystem system design similar to initial LIGO

- » Frequency stabilization to fixed reference cavity,  $10 \text{ Hz/Hz}^{1/2}$  at 10 Hz required ( $10 \text{ Hz/Hz}^{1/2}$  at 12 Hz seen in initial LIGO) ➔
- » Intensity stabilization to in-vacuum photodiode,  $2 \times 10^{-9} \Delta P/P$  at 10 Hz required ( $1 \times 10^{-8}$  at 10 Hz demonstrated) ➔




Max Planck Institute, Hannover leading the Pre-stabilized laser development – **Willke**

- » Close interaction with Laser Zentrum Hannover
- » Experience with GEO-600 laser, reliability, packaging
- » Germany contributing laser to Advanced LIGO



# Input Optics, Modulation




LIGO Laboratory

# Input Optics

- Provides phase modulation for length, angle control (Pound-Drever-Hall)
- Stabilizes beam position, frequency with suspended mode-cleaner cavity
- Matches into main optics (6 cm beam) with suspended telescope
- 1999 White Paper:** Design similar to initial LIGO but 20x higher power

## Challenges:

- » Modulators
- » Faraday Isolators





# Input Optics

University of Florida leading development effort -- Reitze

» As for initial LIGO




**2002:** High power rubidium tantanyl phosphate (RTP) electro-optic modulator developed

» Long-term exposure at Advanced LIGO power densities, with no degradation 

**2003:** Faraday isolator from IAP-Nizhny Novgorod



» thermal birefringence compensated

» Ok to 80 W – more powerful test laser being installed at Livingston






# Test Masses





# Test Masses / Core Optics

- Absolutely central mechanical *and* optical element in the detector
  - » 830 kW; <1ppm loss; <20ppm scatter
  - »  $2 \times 10^8$  Q; 40 kg; 32 cm dia
- **1999 White Paper:** Sapphire as test mass/core optic material; development program launched
- Low mechanical loss, high density, high thermal conductivity all desirable attributes of sapphire
- Fused silica remains a viable fallback option
- Significant progress in program
  - » Industrial cooperation
  - » Characterization by very active LSC working group



Full-size Advanced LIGO  
sapphire substrate

# Core Optics

## 2002: Fabrication of Sapphire:

- » 4 full-size Advanced LIGO boules grown (Crystal Systems); 31.4 x 13 cm; two acquired

## 2003: Mechanical losses: requirement met

- » recently measured at 200 million (uncoated)

## 2002: Bulk Homogeneity: requirement met

- » Sapphire as delivered has 50 nm-rms distortion
- » Goodrich 10 nm-rms compensation polish


## 2001: Polishing technology:

- » CSIRO has polished a 15 cm diam sapphire piece: 1.0 nm-rms uniformity over central 120 mm (requirement is 0.75 nm)


## 2003: Bulk Absorption:

- » Uniformity needs work
- » Average level ~60 ppm, 40 ppm desired
- » Annealing shown to reduce losses

## Compensation Polish




before




after

## Mirror coatings





# Test Mass Coatings

- Optical absorption ( $\sim 0.5$  ppm), scatter meet requirements for (good) conventional coatings
- **R&D mid-2000:** Thermal noise due to coating mechanical loss recognized; LSC program put in motion to develop low-loss coatings
  - » Series of coating runs – materials, thickness, annealing, vendors
  - » Measurements on a variety of samples
- **2001:**  $Ta_2O_5$  identified as principal source of loss  $\rightarrow$
- **2002:** Test coatings show somewhat reduced loss
  - » Alumina/Tantala
  - » Doped Silica/Tantala
- Need  $\sim 5x$  reduction in loss to make compromise to performance minimal
- **2003:** Expanding the coating development program  $\rightarrow$ 
  - » RFP out to 5 vendors; expect to select 2
- Direct measurement via special purpose TNI interferometer – **lab tour**
- First to-be-installed coatings needed in  $\sim 2.5$  years – sets the time scale





# LIGO Thermal Compensation





# Active Thermal Compensation

1999 White Paper: Need recognized, concept laid out

Removes excess 'focus' due to absorption in coating, substrate

Allows optics to be used at all input powers



2002: Initial R&D successfully completed →

- » Quasi-static ring-shaped additional heating
- » Scan to complement irregular absorption

Sophisticated thermal model ('Melody') → developed to calculate needs and solution



2003: Gingin facility (ACIGA) readying tests with Lab suspensions, optics

Application to initial LIGO in preparation





# Seismic Isolation




# Isolation: Requirements

**1999 White Paper:** Render seismic noise a negligible limitation to GW searches

- » Newtonian background will dominate for frequencies less than  $\sim 15$  Hz
- » Suspension and isolation contribute to attenuation

**1999 White Paper:** Reduce or eliminate actuation on test masses

- » Actuation source of direct noise, also increases thermal noise
- » Acquisition challenge greatly reduced
- » In-lock (detection mode) control system challenge is also reduced







# Isolation: Two-stage platform

2000: Choose an active approach: ➡



- » high-gain servo systems, two stages of 6 degree-of-freedom each
- » Allows extensive tuning of system after installation, operational modes
- » Dynamics decoupled from suspension systems

Lead at LSU – Giaime

2003: Stanford Engineering Test Facility Prototype fabricated ➡

- » Mechanical system complete
- » Instrumentation being installed
- » First measurements indicate excellent actuator – structure alignment

2003: RFP for final Prototypes released ➡



LIGO Laboratc



# Isolation: Pre-Isolator


External stage of low-frequency pre-isolation ( $\rightarrow$   $\sim 1$  Hz)

- » Tidal, microseismic peak reduction
- » DC Alignment/position control and offload from the suspensions
- » 1 mm pp range

Lead at Stanford – Lantz

2003: Prototypes in test and evaluation at MIT for early deployment at Livingston in order to reduce the cultural noise impact on initial LIGO


- » System performance exceeds  Advanced LIGO requirements



*LIGO Laboratory*



# Suspension





# Suspensions: Test Mass Quads

**1999 White Paper:** Adopt GEO600 monolithic suspension assembly

Requirements:

- » minimize suspension thermal noise
- » Complement seismic isolation
- » Provide actuation hierarchy

**2000:** Quadruple pendulum design chosen


- » Fused silica fibers, bonded to test mass
- » Leaf springs (VIRGO origin) for vertical compliance

Success of GEO600 a significant comfort ➡

- » **2002:** All fused silica suspensions installed

PPARC funding approved: significant financial, technical contribution; quad suspensions, electronics, and some sapphire substrates ➡

- » U Glasgow, Birmingham, Rutherford
- » Quad lead in UK – **Cantley, Strain, Hough**





# Suspensions: Triples

Triple suspensions for auxiliary optics

- » Relaxed performance requirements


Uses same fused-silica design,  
control hierarchy

2003: Prototype of Mode Cleaner →  
triple suspension fabricated

-- lab tour



To be installed in LASTI fall-2003

- » Fit tests
- » Controls/actuation testing





# GW Readout



# GW readout, Systems

## 1999 White Paper: Signal recycled Michelson Fabry-Perot configuration

- » Offers flexibility in instrument response, optimization for technical noises
- » Can also provide narrowband response
- » Critical advantage: can distribute optical power in interferometer as desired

## 2000: Three table-top prototypes give direction for sensing, locking system ➡➡


## 2003: Glasgow 10m prototype: control matrix elements confirmed ➡➡

## 2003: Readout choice – DC rather than RF for GW sensing ➡➡

- » Offset ~ 1 picometer from interferometer dark fringe
- » Best SNR, simplifies laser, photodetection requirements

## Caltech 40m prototype in construction, early testing – lab tour

- » Complete end-to-end test of readout, controls, data acquisition



# System testing

Initial LIGO experience: thorough testing off-site necessary


Very significant feature in Advanced LIGO plan: testing of accurate prototypes in context

Two major facilities:

- » MIT LASTI facility – full scale tests of seismic isolation, suspensions, laser, mode Cleaner
- » Caltech 40m interferometer – sensing/controls tests of readout, engineering model for data acquisition, software – lab tour

Support from LSC testbeds

- » Gingin – thermal compensation
- » Glasgow 10m – readout
- » Stanford ETF – seismic isolation
- » GEO600 – much more than a prototype!







# Scope of proposal

---

- Upgrade of the detector
  - » All interferometer subsystems
  - » Data acquisition and control infrastructure
- Upgrade of the laboratory data analysis system
  - » Observatory on-line analysis
  - » Caltech and MIT campus off-line analysis and archive
- Virtually no changes in the infrastructure
  - » Buildings, foundations, services, 4km arms unchanged
  - » Present vacuum quality suffices for Advanced LIGO –  $10^{-7}$  torr
  - » Move 2km test mass chambers to 4km point at Hanford
  - » Replacement of ~15m long spool piece in vacuum equipment



# Upgrade of all three interferometers

---

In **discovery** phase, tune all three to broadband curve

- » 3 interferometers nearly doubles the event rate over 2 interferometers
- » Improves non-Gaussian statistics
- » Commissioning on other LHO IFO while observing with LHO-LLO pair

In **observation** phase, the same IFO configuration can be tuned to increase low or high frequency sensitivity

- » sub-micron shift in the operating point of one mirror suffices
- » third IFO could e.g.,
  - observe with a narrow-band VIRGO
  - focus alone on a known-frequency periodic source
  - focus on a narrow frequency band associated with a coalescence, or BH ringing of an inspiral detected by other two IFOs



# Reference design

---

- Baseline is to upgrade the 3<sup>rd</sup> interferometer from 2km to 4km
  - » Cost is modest and sensitivity gain supports discovery
  - » Will certainly want maximum sensitivity later
- Baseline is a nearly simultaneous upgrade of both sites
  - » Could stagger quite significantly to maintain the network – with an equally significant delay in completion and coincidence observations by the two LIGO sites
- Baseline is to employ Sapphire as the test mass material
  - » Fused silica a strong fallback



# Timing of Advanced LIGO

---

- Direct observation of gravitational waves is a compelling scientific goal, and Advanced LIGO will be a crucial element
  - » Revolutionary increase in sensitivity over first generation instruments
  - » Strong astrophysical support for Advanced LIGO signal strengths
- Delaying Advanced LIGO likely to create a significant gap in the field – at least in the US
  - » Can lose the team of instrument scientists
  - » Running costs of an over-exploited instrument represents lost opportunity
- Our LSC-wide R&D program is in concerted motion
  - » Appears possible to meet program goals
- We are well prepared
  - » Reference design well established, confirmation growing through R&D
- Timely for International partners that we move forward now



# Baseline plan




---

- Initial LIGO Observation at design sensitivity 2004 – 2006
  - » Significant observation within LIGO Observatory
  - » Significant networked observation with GEO, VIRGO, TAMA
- Structured R&D program to develop technologies
  - » Conceptual design developed by LSC in 1998
  - » Cooperative Agreement carries R&D to Final Design
- **Now: This proposal is for fabrication, installation**
- Long-lead purchases planned for 2004, real start 2005
  - » Sapphire Test Mass material, seismic isolation fabrication
  - » Prepare a 'stock' of equipment for minimum downtime, rapid installation
- Start installation in 2007
  - » Baseline is a staggered installation, Livingston and then Hanford
- Coincident observations by 2010



# Advanced LIGO

- Initial instruments, data establishing the field of interferometric GW detection
- Advanced LIGO promises exciting astrophysics
- Substantial progress in R&D, design
- Still a few good problems to solve
- A broad community effort, international support
- Ready to make transition from R&D to Project
- **Advanced LIGO can lead the field to maturity**







---

# Advanced LIGO Cost, Schedule and Management

Gary H Sanders  
NSF Review of Advanced LIGO  
Caltech, June 11, 2003





# Main Points


---

- Experienced LIGO Lab team has planned and estimated Advanced LIGO with the LSC
- LIGO Lab and LSC have formed a strong partnership
- Design and development process is already underway in a “project” setting
- Most of the elements of a formal project are in place
- Costs are estimated in detail
- Schedule planning is thorough and will support definition of the final negotiated project
- Performance measurement infrastructure is in place
- International partnerships are already being exercised
- Project Management Plan can be made definitive when financial commitments are complete



---

# Organization



No change in structure required



# A Development Project Across the LSC

---

Since late 1999, we have planned the Advanced LIGO development program as if it was part of a construction project


- » Work Breakdown Structure
- » Cost estimate
- » Schedule
- » Management structure
- » Requirements documented and systems engineering and modeling
- » Design process established

This “projectized” development program has been operating in a serious **collaborative** manner across the LSC

- » LSC Working Groups
  - Advanced detector configurations working group
  - Core optics working group
  - Laser working group
  - Suspensions working group



# LIGO Organization & Support





# LSC “Project” Participation

---

- Lab and LSC scientists/engineers share in leadership roles in the project
- LSC working groups already coordinate progress in monthly meetings and at LSC face-to-face meetings
- LSC Executive Committee involved in discussions of all major design choices and decisions
- Advanced LIGO has become a shared Lab/LSC project



# Advanced LIGO Resource Model

---

- Current FY2002 – FY2006 Cooperative Agreement
  - » LIGO Lab **operating** resources provide staff and support for Advanced LIGO development through Final Design/prototype stage
  - » LIGO Lab **R&D** resources support Advanced LIGO equipment, procurements, incremental staff
- This request supports fabrication and construction, and very little incremental staff for construction and installation
  - » From MREFC or R&RA NSF accounts as NSF determines
- We assume LIGO Lab renewal Cooperative Agreement FY2007 – FY2011 supports staff and infrastructure support for fabrication, construction, installation, commissioning of Advanced LIGO
- LSC/international partner resources support their development programs
- International partner capital budgets support portions of the fabrication, construction, installation
- All of these elements are properly included in the plan shown at this review



---

# Work Breakdown Structure (WBS)





# Advanced LIGO WBS

---

- 1.0 Initial LIGO Construction
- 2.0 LIGO Laboratory Operations
- 3.0 LIGO Laboratory Advanced R&D
- 4.0. Advanced LIGO Project (Advanced LIGO)
  - » 4.1. Facility Modifications (FAC)
  - » 4.2. Seismic Isolation Subsystem (SEI)
  - » 4.3. Suspension Subsystem (SUS)
  - » 4.4 Prestabilized Laser Subsystem (PSL)
  - » 4.5. Input Optics Subsystem (IO)
  - » 4.6. Core Optics Components (COC)
  - » 4.7. Auxiliary Optics Subsystem (AOS)
  - » 4.8. Interferometer Sensing and Controls Subsystem (ISC)
  - » 4.9. Data Acquisition, Diagnostics, Network & Supervisory Control (DAQ)
  - » 4.10. Support Equipment (SUP)
  - » 4.11. Advanced LIGO Construction Project Research and Development (R&D)
  - » 4.12. Data Analysis and Computing Subsystem (COMP)
  - » 4.13. Installation and Commissioning Task (INS)
  - » 4.14. Project Management (PM)

Based upon existing  
LIGO Laboratory  
WBS/account  
structure

## LIGO.2 LIGO Laboratory Operations

### LIGO.2.01 Laboratory Caltech Site Operations

LIGO.2.01.1 Director's Office (DIR)

LIGO.2.01.2 Business Office (BUS)

LIGO.2.01.3 Technical and Engineering Support (TEC)

LIGO.2.01.4 Detector Support (DET)

LIGO.2.01.5 Data Analysis and Computing (COMP)

LIGO.2.01.5.1 Data Analysis (REC)

LIGO.2.01.5.2 Modeling & Simulation (REC)

LIGO.2.01.5.3 Data Analysis - General Comp

LIGO.2.01.6 Campus Research Facilities (CAM)

LIGO.2.01.6.1 40 Meter Interferometer Upgrade

LIGO.2.01.6.1.1 FAC

LIGO.2.01.6.1.1.1 Lab Expansion

LIGO.2.01.6.1.1.2 Vacuum Envelope

LIGO.2.01.6.1.1.3 Vacuum Controls

LIGO.2.01.6.1.2 SEI

LIGO.2.01.6.1.2.1 Output Chamber Stack

LIGO.2.01.6.1.2.2 Cavity Optics Isolation

LIGO.2.01.6.1.2.3 Open

LIGO.2.01.6.1.2.4 Active Isolators

LIGO.2.01.6.1.3 SUS

LIGO.2.01.6.1.3.1 Large Optic Suspensions

LIGO.2.01.6.1.3.2 Small Optic Suspensions

LIGO.2.01.6.1.4 PSL

LIGO.2.01.6.1.4.1 Laser

LIGO.2.01.6.1.4.2 PSL

## LIGO.4 Advanced LIGO Construction

### LIGO.4.01 Facility Modifications (FAC)

LIGO.4.01.1 FAC Vacuum Equipment

LIGO.4.01.1.1 2K to 4K Conversion

LIGO.4.01.1.2 Clean Room Systems

LIGO.4.01.1.3 Vacuum Equipment Bakeout and Preparation

LIGO.4.01.2 FAC Beam Tube

LIGO.4.01.3 FAC Conventional Facilities

LIGO.4.01.3.1 Livingston Staging Building

LIGO.4.01.3.2 Staging Building Cranes

### LIGO.4.02 Seismic Isolation (SEI)

LIGO.4.02.1 SEI Subsystem Management

LIGO.4.02.2 SEI R&D

LIGO.4.02.2.1 Seismic Isolation R&D - Caltech (SEI)

LIGO.4.02.2.2 Stochastic Noise R&D - MIT (STO)

LIGO.4.02.2.3 Seismic Isolation R&D - LSU

LIGO.4.02.2.4 Seismic Isolation R&D - Stanford

LIGO.4.02.2.5 Seismic Isolation R&D - JILA

LIGO.4.02.3 SEI Design

LIGO.4.02.3.1 SEI Conceptual Design/Requirements

LIGO.4.02.3.2 SEI Preliminary Design


LIGO.4.02.3.2.1 ETF Prototype Unit

LIGO.4.02.3.2.1.1 Design

LIGO.4.02.3.2.1.1.1 Requirements Definition

LIGO.4.02.3.2.1.1.2 Mechanical Design

LIGO.4.02.3.2.1.1.3 Electrical Design



**Current status of Advanced LIGO organization –**  
**Org follows WBS**  
**Project Manager just hired**




---

# Project Planning

# Basic Elements of Project Planning Are in Place

- Elements of the PMCS (EVMS)





---

# Cost Estimate



# Estimates Performed To a Standard

---

- Guidance provided to estimators on
  - » Basis of Estimate (BOE)
  - » Work Breakdown Structure (WBS)
  - » Costing Methodology
  - » Cost Database
  - » Collection of Information
  - » Confidence of Cost Estimate
  - » Cost Book
  - » Schedule Integration
  - » Direct Labor Rates
  - » Contract Labor
  - » Risk Analysis
  - » Risk Assessment Methodology
  - » Escalation


**Advanced LIGO**

**COST ESTIMATING PLAN (CEP)**

May 23, 2003

LIGO-M990310-05-M

# Standard Project Life Cycle By Type of Activity





Advanced LIGO					
09-40111-12	2K to 4K Conversion	CAP	LIGO.00009	40111	NSFLIGO.000012
09-40112-12	Clean Room Systems	CAP	LIGO.00009	40112	NSFLIGO.000012
09-40113-12	Vacuum Equipment Bakeout and Preparation	CAP	LIGO.00009	40113	NSFLIGO.000012
09-4012-12	FAC Beam Tube	CAP	LIGO.00009	4012	NSFLIGO.000012
09-40131-12	Livingston Staging Building	CAP	LIGO.00009	40131	NSFLIGO.000012
09-40132-12	Staging Building Cranes	CAP	LIGO.00009	40132	NSFLIGO.000012
09-4021-12	SEI Subsystem Management	ON	LIGO.00009	4021	NSFLIGO.000012

Note: the value "40111" is common.

**LIGO.4 Advanced LIGO Construction**

**LIGO.4.01 Facility Modifications (FAC)**

**LIGO.4.01.1 FAC Vacuum Equipment**

- LIGO.4.01.1.1 2K to 4K Conversion
- LIGO.4.01.1.2 Clean Room Systems
- LIGO.4.01.1.3 Vacuum Equipment Bakeout and Preparation

**LIGO.4.01.2 FAC Beam Tube**

**LIGO.4.01.3 FAC Conventional Facilities**

- LIGO.4.01.3.1 Livingston Staging Building
- LIGO.4.01.3.2 Staging Building Cranes

**LIGO.4.02 Seismic Isolation (SEI)**

- LIGO.4.02.1 SEI Subsystem Management

# Resouce Pool - [Redacted]

**Status: Known Status**

**Discipline: Engineer**

NSF Code:

Organization:

NAME	RES ID	Relation to Proj.	Percentage Availability
Abbott, Richard	ENB2CT02	LIGO Lab	100.00%
Armandula, Helena	ENB2CT04	LIGO Lab	100.00%
Barnes, Maria	ENB2CT08	LIGO Lab	100.00%
Billingsly, Garilynn	ENB2CT10	LIGO Lab	100.00%
Ding, Hongyu	ENB2CT14	LIGO Lab	100.00%
Duncan, Kris	ENB2CT16	LIGO Lab	100.00%
Ehrens, Philip	ENB2CT18	LIGO Lab	100.00%
Frey, Thomas	ENB2CT55	LIGO Lab	100.00%
Hu, Grace	ENB2CT58	LIGO Lab	100.00%

Thursday, July 13, 2000

Page 2 of 22

This value is used as a unique resource ID and populates the resource dictionary for planning.

This value is used as a FTE value for making head counts and evaluating resource usage.

Advanced LIGO Costbook - Microsoft Internet Explorer

File Edit View Favorites Tools Help

Back Forward Stop Home Search Favorites Media Print

Address http://admdbsrv.ligo.caltech.edu/costbook/default.htm

WBS Activity

[Design](#)
[Assembly](#)
[Removal](#)
**Advanced LIGO Costbook**

[Installation](#)
[Commissioning](#)

**CostBook Home** [Help](#)

- ▶ [CostBook Reports](#)
- ▶ Add Line Items
  - [Direct Labor](#)
  - [Contract Labor](#)
  - [Travel](#)
  - [Equipment](#)
  - [Subcontract](#)
  - [Material/Publications/Consultants/Computer Services](#)
- ▶ Edit/Delete Line Items
 

(choose from list, then press Edit)
- ▶ Edit WBS Dictionary
 

(choose from list, then press Edit)
- ▶ Edit Activity Sheet
 

(choose from list, then press Edit)

*Last updated on July 18, 2001*  
 Email: [webmaster@ligo.caltech.edu](mailto:webmaster@ligo.caltech.edu)

[CostBook Home](#)

Done

Advanced LIGO Costbook - Microsoft Internet Explorer

File Edit View Favorites Tools Help

Back Forward Stop Home Search Favorites Media Print

Address http://admdbsrv.ligo.caltech.edu/costbook/report\_default.htm

WBS Activity

[Design](#)
[Assembly](#)
[Removal](#)
**Advanced LIGO Costbook**

[Installation](#)
[Commissioning](#)

**CostBook Reports** [Help](#)

- ▶ PDF Reports as of May 13, 2002
  - [Summary Report](#) (113KB)
  - [4.02 Seismic Isolation Detail](#) (357KB)
  - [4.03 Suspension Detail](#) (501KB)
  - [4.04 PSL Detail](#) (231KB)
  - [4.05 Input Optics Detail](#) (233KB)
  - [4.06 Core Optics Detail](#) (190KB)
  - [4.07 Auxiliary Optics Detail](#) (179KB)
- ▶ Reports by WBS (select a WBS)
- ▶ Reports by System (select a system)
- ▶ Estimator Summary Report (select a name)
- ▶ [Total Cost for LIGO.4](#)

[CostBook Home](#)

Done

Advanced LIGO Costbook - Microsoft Internet Explorer

File Edit View Favorites Tools Help

Back Forward Stop Refresh Home Search Favorites Media Print

Address http://admdbsrv.ligo.caltech.edu/costbook/report\_default.htf

WBS Activity

Design Assembly Removal Installation Commissioning

Advanced LIGO Costbook

CostBook Reports [Help](#)

- ▶ PDF Reports as of May 13, 2002
  - [Summary Report](#) (113KB)
  - [4.02 Seismic Isolation Detail](#) (357KB)
  - [4.03 Suspension Detail](#) (501KB)
  - [4.04 PSL Detail](#) (231KB)
  - [4.05 Input Optics Detail](#) (233KB)
  - [4.06 Core Optics Detail](#) (190KB)
  - [4.07 Auxiliary Optics Detail](#) (179KB)
- ▶ Reports by WBS (select a WBS)

LIGO.4.06.3.2.2 -- Fixture/Handling Design

LIGO.4.06.3.2.3 -- Cleaning Process Design

LIGO.4.06.3.2.4 -- Metrology Design

LIGO.4.06.3.2.5 -- Mechanical Tests Design

LIGO.4.06.3.3 -- COC Final Design

LIGO.4.06.3.3.1 -- Optics Design

▶ LIGO.4.06.3.3.2 -- Fixture/Handling Design

LIGO.4.06.3.3.3 -- Cleaning Process Design

LIGO.4.06.3.3.4 -- Metrology Design

LIGO.4.06.3.3.5 -- Mechanical Tests Design

LIGO.4.06.4 -- COC Fabrication

**LIGO.4.06.4.1 -- Pathfinder**

LIGO.4.06.4.2 -- Metrology Fabrication

LIGO.4.06.4.3 -- Substrate Blanks

LIGO.4.06.4.4 -- Polishing

LIGO.4.06.4.5 -- Coating

▶ LIGO.4.06.4.6 -- Cleaning Process Equipment

LIGO.4.06.4.7 -- Metrology Testing/Qualification

LIGO.4.06.4.8 -- Fixture/Handling Fabrication

LIGO.4.07 -- Auxiliary Optics (AOS)

▶ LIGO.4.07.1 -- AOS Subsystem Management

LIGO.4.07.2 -- AOS R&D

LIGO.4.07.2.1 -- Active Optics Compensation R&D - MIT (AOP)

LIGO.4.07.2.2 -- Active Optics Compensation R&D - Stanford

LIGO.4.07.2.3 -- Active Optics Compensation R&D - ACIGA

LIGO.4.07.2.4 -- Photon Drive R&D - CIT

LIGO.4.07.2.5 -- Photon Drive R&D - MIT

LIGO.4.07.2.6 -- Photon Drive R&D - GEO

LIGO.4.07.3 -- AOS Design

LIGO.4.07.3.1 -- AOS Conceptual Design/Requirements

Done

Advanced LIGO Costbook - Microsoft Internet Explorer

File Edit View Favorites Tools Help

Back Forward Stop Refresh Home Search Favorites Media Print

Address http://admdbsrv.ligo.caltech.edu/costbook/report\_default.htf

WBS Activity

Design Assembly Removal Installation Commissioning

Advanced LIGO Costbook

CostBook Reports [Help](#)

- ▶ PDF Reports as of May 13, 2002
  - [Summary Report](#) (113KB)
  - [4.02 Seismic Isolation Detail](#) (357KB)
  - [4.03 Suspension Detail](#) (501KB)
  - [4.04 PSL Detail](#) (231KB)
  - [4.05 Input Optics Detail](#) (233KB)
  - [4.06 Core Optics Detail](#) (190KB)
  - [4.07 Auxiliary Optics Detail](#) (179KB)
- ▶ Reports by WBS (select a WBS)

LIGO.4.06.4.1 -- Pathfinder

[Browse Activities](#) [WBS Detail](#) [WBS Summary](#)

[Labor Resources](#) [Nonlabor Resources](#) [Dictionary](#)

- ▶ Reports by System (select a system)

[Browse Activities](#) [System Summary](#)

[Labor Resources](#) [Nonlabor Resources](#)

- ▶ Estimator Summary Report (select a name)

[Go](#)

- ▶ [Total Cost for LIGO.4](#)

[CostBook Home](#)

Done Internet

**LIGO II CostBook Activity Sheet Summary for a WBS - Microsoft Internet Explorer**

File Edit View Favorites Tools Help

Back Forward Stop Refresh Home Search Favorites Media Print Mail Stop

Address [http://admdbsrv.ligo.caltech.edu/costbook/report\\_wbsSummary.htm?rtype=wbs&callingform=sum&wbs:](http://admdbsrv.ligo.caltech.edu/costbook/report_wbsSummary.htm?rtype=wbs&callingform=sum&wbs:) Go Links

### CostBook Activity Sheet Summary

for WBS Number LIGO.4.06.4.1 -- Pathfinder  
(Amounts Include Staff Benefits, GRA Benefits, and Indirect Cost)

---

WBSNo: LIGO.4.06.4.1 - Pathfinder

<a href="#">COF40641A</a> - EST: Pathfinder SPF	\$490,276.25
<a href="#">COF40641B</a> - EST: Pathfinder LPF	\$833,015.50
<b>WBS Total:</b>	<b>\$1,323,291.75</b>
<b>Report Total:</b>	<b>\$1,323,291.75</b>
<b>Report Contingency at 63.40%:</b>	<b>\$839,007.79</b>
<b>Total Plus Contingency:</b>	<b>\$2,162,299.54</b>

Done Internet

**LIGO II Costbook Activity Sheet Detail - Microsoft Internet Explorer**

File Edit View Favorites Tools Help

Back Forward Stop Refresh Home Search Favorites Media Print

Address: [http://admbsrv.ligo.caltech.edu/costbook/report\\_sheetDetail.htm?sheet=COF40641A&wbsstring=LIGO.4.06.4.1%2APathfinder&rtype=wbs&callingform=sum](http://admbsrv.ligo.caltech.edu/costbook/report_sheetDetail.htm?sheet=COF40641A&wbsstring=LIGO.4.06.4.1%2APathfinder&rtype=wbs&callingform=sum) Go Links

### Costbook Activity Sheet Detail


WBSNo:LIGO.4.06.4.1 - Pathfinder  
 Activity:COF40641A - EST: Pathfinder SPF  
 Duration:365 days  
 Estimator:G. Billingsley on 05/02/2001

Item Code	Cost Category	Resource	Description	Comments or Vendor	Cost Basis	Cost Code	Quantity	Unit Cost	Item Amount
B2	Labor	EN	Engineer		EE	12-40641-14 CP	507	\$45.00	\$22,815.00
B2	Labor	OT	Other		EE	12-40641-14 CP	179	\$50.00	\$8,950.00
B2	Labor	SC	Scientist		EE	12-40641-14 CP	108	\$40.00	\$4,320.00
D2	Equip.	D2	Small Pathfinder blank cost - rollup of 6		HD	12-40641-14 CP	1	\$43,010.00	\$43,010.00
E1	Int Travel	E1	Deliver Mirrors to UWA, review specifications		HD	12-40641-14 CP	1	\$2,075.00	\$2,075.00
G5	Contract	G5	Coat 5 types of mirrors	? Virgo-Lyon	EE	12-40641-14 CP	1	\$200,000.00	\$200,000.00
G5	Contract	G5	Polish 3 Mode cleaner mirrors	Wave Precision	VQ	12-40641-14 CP	1	\$68,445.00	\$68,445.00
G5	Contract	G5	polish 3 optics	CSIRO	VQ	12-40641-14 CP	1	\$129,640.00	\$129,640.00
G5	Contract	G5	Shipping	Time Trax	HD	12-40641-14 CP	1	\$2,000.00	\$2,000.00
<b>Subtotal:</b>									<b>\$481,255.00</b>
<b>Staff Benefits:</b>									<b>\$9,021.25</b>
<b>GRA Benefits:</b>									<b>\$0.00</b>
<b>Indirect Cost:</b>									<b>\$0.00</b>
<b>Total Cost:</b>									<b>\$490,276.25</b>
( Cost: 6x1.00% + Sched: 4x1.00% + Tech: 8x4.00%) Contingency @ 42.00%:									<b>\$205,916.02</b>
<b>Cost Plus Contingency:</b>									<b>\$696,192.27</b>

[Return to WBS Summary page](#)

Done Internet

Activity ID	Activity Description	Orig Dur	Early Start	Early Finish	Late Start	Late Finish	Total Float	Budgeted Cost
<b>LIGO</b>								
<b>LIGO.4 Advanced LIGO Construction</b>								
Subtotal		762	18OCT00	03NOV03	12OCT01	20MAR07	841	2,162,299.54
<b>LIGO.4.06 Core Optics Components (COC)</b>								
<b>LIGO.4.06.4 COC Fabrication</b>								
<b>LIGO.4.06.4.1 Pathfinder</b>								
CO-F40641A	EST: Pathfinder SPF	654*	18OCT00	02JUN03	29SEP05	20MAR07	949	696,192.27
CO-F40641B	EST: Pathfinder LPF	742*	15NOV00	03NOV03	12OCT01	03NOV03	0	1,466,107.27
CO-D50540	Small Pathfinder-Prepare Blank specifications	10	18OCT00	31OCT00	29SEP05	12OCT05	1,238	0.00
CO-P50550	SPF-Order Blanks	5	02JAN02*	08JAN02	13OCT05	19OCT05	949	0.00
CO-P50560	SPF- Polishing RFP	20	18OCT00	14NOV00	21FEB06	20MAR06	1,333	0.00
CO-P50570	SPF - Polish Proposal prep at vendor	20	15NOV00	14DEC00	21MAR06	17APR06	1,333	0.00
CO-P50580	SPF-Polishing Proposal Evaluation	10	15DEC00	02JAN01	18APR06	01MAY06	1,333	0.00
CO-P50590	SPF-Let Polishing Contract	10	03JAN01	17JAN01	02MAY06	15MAY06	1,333	0.00
CO-P50600	SPF- Coating RFP	10	18OCT00	31OCT00	31AUG06	14SEP06	1,468	0.00
CO-P50610	SPF - Coating Proposal prep at vendor	20	01NOV00	30NOV00	15SEP06	12OCT06	1,468	0.00
CO-P50620	SPF-Coating Proposal Evaluation	10	01DEC00	14DEC00	13OCT06	26OCT06	1,468	0.00
CO-P50630	SPF-Let Coating Contract	5	15DEC00	21DEC00	27OCT06	02NOV06	1,468	0.00
CO-T50640	SPF-Coating Set Up	20	22DEC00	24JAN01	03NOV06	04DEC06	1,468	0.00
CO-F50650	SPF-Fabricate Blanks, Halfi size	100	09JAN02	31MAY02	20OCT05	20MAR06	949	0.00
CO-Q50660	SPF-Absorb Testing	20	03JUN02	28JUN02	21MAR06	17APR06	949	0.00
CO-Q50670	SPF-Homogeneity Measurement	20	01JUL02	29JUL02	18APR06	15MAY06	949	0.00
CO-F50680	SPF-PF-Polishing	120	30JUL02	23JAN03	16MAY06	02NOV06	949	0.00
CO-Q50690	SPF- Uncoated Metrology	20	24JAN03	21FEB03	03NOV06	04DEC06	949	0.00
CO-T50700	SPF-Coating	40	24FEB03	18APR03	05DEC06	05FEB07	949	0.00
CO-Q50710	SPF-Coated Metrology	20	21APR03	16MAY03	06FEB07	06MAR07	949	0.00
CO-H50720	SPF-Deliver to UWA	10	19MAY03	02JUN03	07MAR07	20MAR07	949	0.00
CO-D50740	LPF-Prepare Blank specifications Full size	10	15NOV00	30NOV00	12OCT01	25OCT01	227	0.00
CO-P50750	LPF-Order Blanks - Pathfinder full size	10	01DEC00	14DEC00	26OCT01	08NOV01	227	0.00
CO-P50760	LPF- Polishing RFP	10	11DEC02	26DEC02	11DEC02	26DEC02	0	0.00
CO-P50770	LPF - Polish Proposal prep at vendor	10	27DEC02	13JAN03	27DEC02	13JAN03	0	0.00
CO-P50780	LPF-Let Polishing Contract	10	14JAN03	28JAN03	14JAN03	28JAN03	0	0.00
CO-P50790	LPF- Coating RFP	10	11DEC02	26DEC02	10APR03	23APR03	80	0.00
CO-P50800	LPF - Coating Proposal prep at vendor	10	27DEC02	13JAN03	24APR03	07MAY03	80	0.00
CO-P50810	LPF-Let Coating Contract	5	14JAN03	21JAN03	08MAY03	14MAY03	80	0.00
CO-T50820	LPF-Coating Set Up	20	22JAN03	19FEB03	15MAY03	12JUN03	80	0.00
CO-F50830	LPF-Fabricate Blanks, Full size	260	09NOV01*	22NOV02	09NOV01	22NOV02	0	0.00
CO-Q50840	LPF-Absorb Testing	20	25NOV02	26DEC02	25NOV02	26DEC02	0	0.00
CO-Q50850	LPF-Homogeneity Measurement	20	27DEC02	28JAN03	27DEC02	28JAN03	0	0.00
CO-F50860	LPF-Polishing	80	29JAN03	21MAY03	29JAN03	21MAY03	0	0.00
CO-Q50870	LPF- Uncoated Metrology	15	22MAY03	12JUN03	22MAY03	12JUN03	0	0.00
CO-F50880	LPF-Coating	80	13JUN03	06OCT03	13JUN03	06OCT03	0	0.00
CO-Q50890	LPF-Coated Metrology	20	07OCT03	03NOV03	07OCT03	03NOV03	0	0.00
CO-H50900	Deliver LPF ETM to LASTI	0		03NOV03		03NOV03	0	0.00
CO-H50930	Deliver LPF ITM to LASTI	0		03NOV03		03NOV03	0	0.00





Cost										
- + D2*										
Resource	D2*	E1*	EN*	G5*	OT*	SC*	Z-RISK	Z-RISK	Z-RISK	Z-RISK
Cost Acct/Category	12-40641-14E	12-40641-14I	12-40641-14L	12-40641-14C	12-40641-14L	12-40641-14L	12-40641-14C	12-40641-14E	12-40641-14I	12-40641-14L
Driving	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Curve										
Budgeted cost	43010.00	2075.00	28518.75	400085.00	11187.50	5400.00	168035.70	18064.20	871.50	18944.62
Actual this period	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
Actual to date	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
Percent expended	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Percent complete										
Earned value	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
Cost to complete	43010.00	2075.00	28518.75	400085.00	11187.50	5400.00	168035.70	18064.20	871.50	18944.62
At completion	43010.00	2075.00	28518.75	400085.00	11187.50	5400.00	168035.70	18064.20	871.50	18944.62
Variance	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00

Budget Summary			
- + D2*			
Resource	Cost Acct/Category	Driving	Curve
D2*	12-40641-14E	<input type="checkbox"/>	▲
E1*	12-40641-14I	<input type="checkbox"/>	▼
EN*	12-40641-14L	<input type="checkbox"/>	▼
G5*	12-40641-14C	<input type="checkbox"/>	▼

	Units	Cost	Total Units	Total Cost
Units per day	0.00			
Res Lag/Duration	0			
% Complete/Expended		0.0	0.0	0.0
Budgeted amount	1.00	43010.00	800.00	696192.27
Planned value	0.00	0.00	0.00	0.00
Earned value	0.00	0.00	0.00	0.00
Actual to date	0.00	0.00	0.00	0.00
To complete	1.00	43010.00	800.00	696192.27
At completion	1.00	43010.00	800.00	696192.27
Variance	0.00	0.00	0.00	0.00





Advanced LIGO Cost Estimate Detail

WBS Number	LIGO.4.06.4.1
WBS Description	Pathfinder
Activity	COF40641A
Description	EST: Pathfinder SPF
Location	Capital Project
Cost Code	12-40641-14

Duration	365 days
Estimated By	G. Billingsley
Last Modified On	07/12/2001

Line	Item Code	Cost Category	Comments or Vendor	Cost Basis	Quantity (Hrs/EA)	Direct Labor (AA, B1-B6)		Contract Labor (G5)		Equipment (D1,D2)		Travel (E1,E2)		Material (S1-S4)		Subcontracts (S5)		Total Cost (\$)	Reference
						Unit Cost (\$)	Total (\$)	Unit Cost (\$)	Total (\$)	Unit Cost (\$)	Total (\$)	Unit Cost (\$)	Total (\$)	Unit Cost (\$)	Total (\$)	Unit Cost (\$)	Total (\$)		
1	R2	Labor			507	15	22,815											22,815	COF020400
2	R2	Labor					8,950											8,950	COF020400
3	R2	Labor																1,320	COF020400
4	D2	Equip								13,010								13,010	COF020400
5	E1	Int Travel										2,075						2,075	COF020400
6	G2	Contract - G												129,640		129,640		129,640	COF020401
7	G2	Contract - G2												58,415		58,415		58,415	COF020401
8	G2	Contract - G2																2,900	COF020401
9	G2	Contract - G2																	

Activity Sheet Header

Advanced LIGO Cost Estimate Detail

Labor Summary (Direct Labor plus)

Key/Fac	Post/Doc
Hours	Person Years

WBS Number	LIGO.4.06.4.1
WBS Description	Pathfinder
Activity	COF40641A
Description	EST: Pathfinder SPF
Location	Capital Project
Cost Code	12-40641-14

Duration	365 days
Estimated By	G. Billingsley
Last Modified On	07/12/2001

**WBS Definition**

In addition to serving as a summary WBS element, fabrication associated with the R&D elements of this WBS element. The purpose of the Pathfinder industrial partners to achieve the requirements for:

- Suppliers Blanks in the large size requires low bulk absorption at 1001 microns. Although cap under WBS elements 0.16.2.2 and 0.16.2.1 these are enabling research to be able to attempt production of requirements. The cost for the large scale blanks is to proof of capability and the first step in the Pathfinder project.
- Suppliers polishing to the 100 Å surface finish, the large sizes required. Initially polishing will be attempted by WBS elements 0.16.2.2 and 0.16.2.1. Later this WBS element will be polished to demonstrate the capability meet the size requirements on full scale optics.
- Coating on large diameter optics to equal or better than the LIGO requirement for absorption in the highest reflective coatings. The purpose of this WBS element is the qualification of a new coating vendor and possibly a new coating prescription for lower absorption at full scale sizes whether on fused silica or sapphire. The small scale coating research WBS element 0.16.2.1 is to define a suitable coating for sapphire substrates and to coating prescription for a lower absorption high reflectance coating on fused silica. The results of this small scale coating research are applied under the WBS element at full scale in a production facility.

Travel:	COF49050	SPF Left Polishing Contract	10
Assume 2 trips to RUSV vendor Germany	COF49050	SPF Order Blanks	5
	COF49050	SPF Fabricate Blanks Half size	100
Assume 1 trip to OMA vendor NY	COF29060	SPF Absorb Testing	20
	COF290670	SPF Homogeneity Measurement	20
Assume 2 trips to Sapphire vendor Boston	COF49060	SPF PF Polishing	120
Shipping:	COF290690	SPF Uncoated Metrology	20
	COF50000	SPF Coating	10
150 to ship each optic from vendor to Caltech. Based on verbal estimate from shipping clerk.	COF290710	SPF Coated Metrology	20
Labor:	COF490720	SPF Delivered to UVA	10
Based upon LIGO experience.			

Advanced LIGO Cost Estimate Detail

WBS Number	12-060111
WBS Description	Pathfinder
Activity	01-06-011
Description	ISE Pathfinder SPI
Location	Capital Project
Cost Code	12-060111

Duration	95 days
Estimated By	G. Bilingsley
Last Modified On	07/12/2001

Line	NSF Item Code	Cost Category	LIGO Resource Code	Description	Estimator Comments or Vendor	Cost Basis	Quantity (Hrs/Ea)	Direct Labor (AA, B1-B6)		Contract Labor (G5)		Equipment (D1,D2)		Travel (E1,E2)		Material (S1-S4)		Subcontracts (G5)		Total Cost (\$)	Reference		
								Unit Cost (\$)	Total (\$)	Unit Cost (\$)	Total (\$)	Unit Cost (\$)	Total (\$)	Unit Cost (\$)	Total (\$)	Unit Cost (\$)	Total (\$)	Unit Cost (\$)	Total (\$)				
1 B2	Labor	EN	Engineer			EE	507	15	22,815											22,815	010202-00		
2 B2	Labor	OT	Other			EE	179	50	8,950											8,950	010202-00		
3 B2	Labor	SC	Scientist			EE	198	49	1,320											1,320	010202-00		
4 D2	Equip.	D2		Small Pathfinder Blank cost - rollup of 6		HD	1					13,000	13,000							13,000	010202-00		
5 E1	Int Travel	E1		Deliver Mirrors to UWA, review specifications		HD	1					2,075	2,075							2,075	010202-00		
6 G5	Contract	G5		polish 3 optics	CSIRO	VQ	1									129,600	129,600			129,600	010202-00		
7 G5	Contract	G5		Polish 3 Mode cleaner mirrors	Wave Precision	VQ	1									68,415	68,415			68,415	010408-00		
8 G5	Contract	G5		Shipping	Time Trax	HD	1									2,000	2,000			2,000			
9 G5	Contract	G5		Coat 5 types of mirrors	2 Virgo-Lyon	EE	1									200,000	200,000			200,000			
									30,085		100,085		13,000		2,075				100,085		481,255		
																			Staff Benefits at	25.00%		120,314	
																			(50) GRA Benefits at	58.00%		0	
																			Indirect Cost at	0.00%		0	
																			Total Cost			490,279	

Labor Summary (t)

Hours	Ke
Person Years	

WBS Definition

In a limited series of fabrication associated with this WBS element. The primary industrial partners to achieve the bulk absorption at 10.6 micrometer WBS element 0.1.6.2, enabling research to be able to requirements. The cost for the first proof of capability and the first 3000. Suppliers pertaining to the large sizes required. Initially provided by WBS element 0.1.6.2, this WBS element will be polished on full scale optics.

Coating on large diameter optics absorption in the highest reflectance coating qualification of a new coating vendor on absorption on full scale size whether on research WBS element 0.1.6.2. This is a coating prescription for a lower absorption of this small scale coating research are applied production facilities.

### Activity Sheet Takeoff Area

Line	NSF Item Code	Cost Category	LIGO Resource Code	Description	Estimator Comments or Vendor	Cost Basis	Quantity (Hrs/Ea)
1	B2	Labor	EN	Engineer		EE	507
2	B2	Labor	OT	Other		EE	179
3	B2	Labor	SC	Scientist		EE	198
4	D2	Equip.	D2	Small Pathfinder blank cost - rollup of 6		HD	1
5	E1	Int Travel	E1	Deliver Mirrors to UWA, review specifications		HD	1
6	G5	Contract	G5	polish 3 optics	CSIRO	VQ	1
7	G5	Contract	G5	Polish 3 Mode cleaner mirrors	Wave Precision	VQ	1
8	G5	Contract	G5	Shipping	Time Trax	HD	1
9	G5	Contract	G5	Coat 5 types of mirrors	2 Virgo-Lyon	EE	1

Advanced LIGO Cost Estimate Detail

WBS Number	100-030-11
WBS Description	Pathfinder
Activity	COF40641A
Description	EST: Pathfinder SPI
Location	Capital Project
Cost Code	12-06011-11

Duration	65 days
Estimated By	A. Billingsley
Last Modified On	07/12/2001

Line	HSF Item Code	LIGO Resource Category	Description	Estimator Comments or Vendor	Cost Basis	Quantity (Hrs/Ea)	Direct Labor (AA, B1-B6)		Contract Labor (G5)		Equipment (D1,D2)		Travel (E1,E2)		Material (G1-G4)		Subcontracts (G5)		Total Cost (\$)	Reference
							Unit Cost	Total (\$)	Unit Cost	Total (\$)	Unit Cost	Total (\$)	Unit Cost	Total (\$)	Unit Cost	Total (\$)	Unit Cost	Total (\$)		
1	B2	Labor	LN	Unmet	FF	57	15	22,815											22,815	CO10202-00
2	B2	Labor	01	Other	FF	170	50	8,950											8,950	CO10202-00
3	B2	Labor	80	Scientist	FF	108	40	4,320											4,320	CO10202-00
4	D2	Equip.	D2	Small Pathfinder Blank cost - 100µm	HD	1					13,910								13,910	CO10202-00
5	E1	Int Travel	E1	Delivery Mirrors to UWA, review specifications	HD	1						2,075	2,075						2,075	CO10202-00
6	G2	Contract	G2	polish 3 optics	VO									129,640	129,640			129,640	CO10202-01	
7	G2	Contract	G2	Polish 3 Mask cleanroom	VO									68,445	68,445			68,445	CO10168-00	
8	G2	Contract	G2	Shipping	VO									2,000	2,000			2,000		
9	G2	Contract	G2	Cost Supply of mirrors	VO									200,000	200,000			200,000		
Subtotal COF40641A EST: Pathfinder																				
400,085 481,255 9,021																				

Labor Summary (Direct Labor plus Contract Labor)

Key/Fac	PostDoc	Mgn
Hours		
Person Years		

WBS Definition

In addition to serving as a summary WBS element for the R&D element of the WBS element, the purpose of the Pathfinder industrial partners to achieve the requirements:

- Supply Blanks in the large sizes required for bulk absorption at 100µm. Although under WBS elements 01, 02, 22 and 01, 02, 22, enabling research to be able to attempt proof-of-capability and the first step in the production of large scale optics.
- Supply polishing to the 100µm on the large sizes required. Initially polishing provided by WBS elements 01, 02, 22 and 01, 02, 22, will be polished to demand full scale optics.
- Coatings on large diameter optics to be absorption in the high reflectance coatings, qualification of a large coating vendor and production at full scale size, whether on the research WBS element 01, 02, 22, or on the coating prescription for a lower absorption of this small scale coating research and application production facility.

Cost Extension Area

Direct Labor (AA, B1-B6)		Contract Labor (G5)		Equipment (D1,D2)		Travel (E1,E2)		Material (G1-G4)		Subcontracts (G5)		Total Cost (\$)	Reference
Unit Cost	Total (\$)	Unit Cost	Total (\$)	Unit Cost	Total (\$)	Unit Cost	Total (\$)	Unit Cost	Total (\$)	Unit Cost	Total (\$)		
45	22,815											22,815	CO10202-00
50	8,950											8,950	CO10202-00
40	4,320											4,320	CO10202-00
				43,010	43,010							43,010	CO10202-00
							2,075	2,075				2,075	CO10202-00
									129,640	129,640		129,640	CO10202-01
									68,445	68,445		68,445	CO10168-00
									2,000	2,000		2,000	
									200,000	200,000		200,000	
36,085		400,085		43,010		2,075				400,085		481,255	

Advanced LIGO Cost Estimate Detail

WBS Number	L102.010.11
WBS Description	Pathfinder
Activity	COF40641A
Description	EST: Pathfinder SPF
Location	Capital Project
Cost Code	12-0641-11

Duration	65 days
Estimated By	G. Billingsley
Last Modified On	07/12/2001

Line	HSF Item Code	Cost Category	LIGO Resource Code	Description	Estimator Comments or Vendor	Cost Basis	Quantity (HR/Ea)	Direct Labor (AA, B1-B6)		Contract Labor (G5)		Equipment (D1,D2)		Travel (E1,E2)		Material (S1-S4)		Subcontracts (G5)		Total Cost (\$)	Reference			
								Unit Cost	Total (\$)	Unit Cost	Total (\$)	Unit Cost	Total (\$)	Unit Cost	Total (\$)	Unit Cost	Total (\$)	Unit Cost	Total (\$)			Unit Cost	Total (\$)	
1	B2	Labor	EN	Engineer		FF	907	15	22,815											22,815	COF0202-00			
2	B2	Labor	OT	Other		FF	170	50	8,950											8,950	COF0202-00			
3	B2	Labor	ST	Scientist		FF	108	40	1,320											1,320	COF0202-00			
4	D2	Equip.	D2	Small Pathfinder Blank cost rollup of 4		HD	1					13,000								13,000	COF0202-00			
5	E1	Int Travel	E1	Deliver Minor and WA review specifications		HD	1						2,075	2,075						2,075	COF0202-00			
6	G3	Contract	G3	polish 3 optics	OSIRO	VO	1									129,640			129,640	129,640	COF0202-00			
7	G3	Contract	G3	Polish 3 Mock cleanroom mirrors	Wing Precision	VO	1									68,415			68,415	68,415	COF0202-00			
8	G3	Contract	G3	Shipping	Time Trax	HD	1									2,000			2,000	2,000				
9	G3	Contract	G3	Cost types of mirrors	Wing Precision	FF	1										200,000			200,000	200,000			
Subtotal: COF40641A EST: Pathfinder SPF										2,085		100,085			13,000		2,075				100,085		181,255	

Labor Summary (Direct Labor plus Contract Labor)

--- AA --- B1 --- B2 --- B3 --- B4 --- B5 ---												
Key/Fac	PostDoc	Mgmt	StSci	Sci	StEngr	Engr	Tech	Other	Total	Grad	UGrad	Admin
Hours				108		507		179	794			
Person Years				0.1		0.3		0.1	0.4			

Risk Factors	Technical	Cost	Schedule
Risk Multipliers	8	6	4

WBS Definition

In addition to serving as a summary WBS element for all COC fabrication associated with the R&D elements, the Pathfinder WBS element also serves as a summary WBS element for all COC fabrication associated with the industrial test...

Duration	20
	10
	10
	20
	10
	10
	5
	20
	10
	5
	100
	20
	20
	120
	20
	10
	20
	10

Risk and Cost Totals

Risk Factors		Risk Multipliers	
Technical	8	4.00%	
Cost	6	1.00%	
Schedule	4	1.00%	
Calculated Contingency	42.00%		
Estimator Override			

Staff Benefits at 25.00%	9,021
(G6) GRA Benefits at 58.00%	0
Indirect Cost at 0.00%	0
Total Cost	490,276
Contingency at 42.00%	205,916
Cost Plus Contingency	696,192

Advanced LIGO Cost Estimate Detail

WBS Number	COF406414
WBS Description	Pathfinder
Activity	COF406414
Description	EST: Pathfinder SFF
Location	Capital Project
Cost Code	COF406414

Duration	65 days
Estimated By	G. Bilingsley
Last Modified On	07/12/2001

Line	HSF Item Code	LIGO Resource Category	Description	Estimator Comments or Vendor	Cost Basis	Quantity (Hrs/Eq)	Direct Labor (AA, B1-B6)		Contract Labor (G5)		Equipment (D1,D2)		Travel (E1,E2)		Material (G1-G4)		Subcontracts (G5)		Total Cost (\$)	Reference		
							Unit Cost (\$)	Total (\$)	Unit Cost (\$)	Total (\$)	Unit Cost (\$)	Total (\$)	Unit Cost (\$)	Total (\$)	Unit Cost (\$)	Total (\$)	Unit Cost (\$)	Total (\$)				
1 R2	Labor	LN	Turner		FF	97	15	22,815											22,815	COF020240		
2 R2	Labor	OL	Other		FF	150	50	8,950											8,950	COF020240		
3 R2	Labor	SO	Scientist		FF	108	10	1,320											1,320	COF020240		
4 D2	Equip.	D2	Small Pathfinder Blank cost for flip of 6		HD	1					13,000	13,000							13,000	COF020240		
5 H1	Int Travel	H1	Deliver Mirrors to UWA, review specifications		HD	1						2,075	2,075						2,075	COF020240		
6 G3	Contract	G3	polish 3 optics	CSIRO	VO	1										129,640	129,640		129,640	COF020240		
7 G3	Contract	G3	Polish 3 Mode cleaner mirrors	Wave Precision	VO	1										68,415	68,415		68,415	COF020240		
8 G3	Contract	G3	Shipping	Luna Trax	HD	1										2,000	2,000		2,000			
9 G3	Contract	G3	Cost 5 types of mirrors	Wave Precision	FF	1										200,000	200,000		200,000			
Subtotal: COF406414 EST: Pathfinder SFF								30,085		100,055		13,000		2,075				100,055		181,255		
																			Staff Benefits at	25.00%	5,921	
																			(5%) GRA Benefits at	58.00%	0	
																			Indirect Cost at	0.00%	0	
																			Total Cost		197,176	
																			Contingency at	42.00%	205,916	
																			Cost Plus Contingency		693,192	

Labor Summary (Direct Labor plus Contract Labor)

AA	B1	B2					B3	B4	B5
Key/Fac	PostDoc	Mgmt	SrSci	Sci	SrEngr	Engr	Tech	Other	Admin
Hours				108		507			
Person Years				0.1		0.3			

Risk Factors		Risk Multipliers	
Technical	3	1.00%	
Cost	3	1.00%	
	4	1.00%	
Calculated Contingency		1.00%	
Estimator Override			

WBS Definition

In addition to serving as a summary WBS, this WBS also defines the fabrication associated with the RFP. The WBS also defines the industrial pattern...

Task List

Task No	Description	Duration
1	SFF - Polishing RFP	20
2	Polishing RFP	10
3	Polishing RFP	10
4	Polishing RFP	10
5	Polishing RFP	10
6	Polishing RFP	10
7	Polishing RFP	10
8	Polishing RFP	10
9	Polishing RFP	10
10	Polishing RFP	10
11	Polishing RFP	10
12	Polishing RFP	10
13	Polishing RFP	10
14	Polishing RFP	10
15	Polishing RFP	10
16	Polishing RFP	10
17	Polishing RFP	10
18	Polishing RFP	10
19	Polishing RFP	10
20	Polishing RFP	10
21	Polishing RFP	10
22	Polishing RFP	10
23	Polishing RFP	10
24	Polishing RFP	10
25	Polishing RFP	10
26	Polishing RFP	10
27	Polishing RFP	10
28	Polishing RFP	10
29	Polishing RFP	10
30	Polishing RFP	10
31	Polishing RFP	10
32	Polishing RFP	10
33	Polishing RFP	10
34	Polishing RFP	10
35	Polishing RFP	10
36	Polishing RFP	10
37	Polishing RFP	10
38	Polishing RFP	10
39	Polishing RFP	10
40	Polishing RFP	10
41	Polishing RFP	10
42	Polishing RFP	10
43	Polishing RFP	10
44	Polishing RFP	10
45	Polishing RFP	10
46	Polishing RFP	10
47	Polishing RFP	10
48	Polishing RFP	10
49	Polishing RFP	10
50	Polishing RFP	10
51	Polishing RFP	10
52	Polishing RFP	10
53	Polishing RFP	10
54	Polishing RFP	10
55	Polishing RFP	10
56	Polishing RFP	10
57	Polishing RFP	10
58	Polishing RFP	10
59	Polishing RFP	10
60	Polishing RFP	10
61	Polishing RFP	10
62	Polishing RFP	10
63	Polishing RFP	10
64	Polishing RFP	10
65	Polishing RFP	10
66	Polishing RFP	10
67	Polishing RFP	10
68	Polishing RFP	10
69	Polishing RFP	10
70	Polishing RFP	10
71	Polishing RFP	10
72	Polishing RFP	10
73	Polishing RFP	10
74	Polishing RFP	10
75	Polishing RFP	10
76	Polishing RFP	10
77	Polishing RFP	10
78	Polishing RFP	10
79	Polishing RFP	10
80	Polishing RFP	10
81	Polishing RFP	10
82	Polishing RFP	10
83	Polishing RFP	10
84	Polishing RFP	10
85	Polishing RFP	10
86	Polishing RFP	10
87	Polishing RFP	10
88	Polishing RFP	10
89	Polishing RFP	10
90	Polishing RFP	10
91	Polishing RFP	10
92	Polishing RFP	10
93	Polishing RFP	10
94	Polishing RFP	10
95	Polishing RFP	10
96	Polishing RFP	10
97	Polishing RFP	10
98	Polishing RFP	10
99	Polishing RFP	10
100	Polishing RFP	10

Labor Summary (FTEs)

Labor Summary (Direct Labor plus Contract Labor)

AA	B1	B2					B3	B4	B5			
Key/Fac	PostDoc	Mgmt	SrSci	Sci	SrEngr	Engr	Tech	Other	Total	Grad	UGrad	Admin
Hours				108		507		179	794			
Person Years				0.1		0.3		0.1	0.4			



Advanced LIGO Cost Estimate Detail

WBS Number	100-100-11
WBS Description	Pulsifier
Activity	OE 100-11A
Description	ISE Pulsifier SPI
Location	Capital Project
Cost Code	12-100111

Duration	65 days
Estimated By	A. Billingsley
Last Modified On	07/12/2009

Line	HSF Item Code	Cost Category	LIGO Resource Code	Description	Estimator Comments or Vendor	Cost Basis	Quantity (Hrs/Ea)	Direct Labor (A, B1-B6)		Contract Labor (G5)		Equipment (D1,D2)		Travel (E1,E2)		Material (G1-G4)		Subcontracts (G5)		Total Cost (\$)	Reference	
								Unit Cost (\$)	Total (\$)	Unit Cost (\$)	Total (\$)	Unit Cost (\$)	Total (\$)	Unit Cost (\$)	Total (\$)	Unit Cost (\$)	Total (\$)	Unit Cost (\$)	Total (\$)			
1	R2	Labor	1N	Engineer		11	507	11	22,815											22,815	010202-00	
2	R2	Labor	01	Other		11	179	11	8,950											8,950	010202-00	
3	R2	Labor	S0	Scientist		11	108	11	1,320											1,320	010202-00	
4	D2	Equip.	D2	Small Pulsifier Blank cost - fillup of 2		110	1					13,000	13,000							13,000	010202-00	
5	11	Int Travel	11	Deliver Mirrors to UVA, review specifications		110	1						2,075	2,075						2,075	010202-00	
6	G3	Contract	G3	polish 3 optics	CSIRO	300	1									129,640	129,640			129,640	010202-01	
7	G3	Contract	G3	Polish 3 Mode cleaner mirrors	Wing Precision	300	1									68,415	68,415			68,415	010408-00	
8	G3	Contract	G3	Shipping	Time Trax	110	1									2,000	2,000			2,000		
9	G3	Contract	G3	Cost types of mirrors	UVA/LLNL	11	1									200,000	200,000			200,000		
																			100,085	481,255		

Labor Summary (Direct Labor plus Contract Labor)

Key/Fac	PostDoc	Mgmt	St Sc
Hours			
Person Years			

### Basis of Estimate

Based on Material costs quoted by vendors as follows:

40 Kg sapphire masses 2 ITMs, 4ITM spares, \$97,986 ea.

2 ETMs, 4 ETM spares \$97,986 ea

Grade 0AA fused silica 1 PRM and 2 spares at \$22,076 ea

1 SRM and 2 spares at \$22,076 ea

Grade 311 SV fused silica

1 BS and 2 spares at \$142,291 ea

Travel:

Assume 2 trips to 311SV vendor (Germany)

Assume 1 trip to 0AA vendor (NY)

Assume 2 trips to Sapphire vendor (Boston)

Shipping:

190 to ship each optic from vendor to Caltech. Based on verbal estimate from shipping clerk.

Labor:

Based upon LIGO 1 experience.

Staff Benefits at	25.00%	19,211
(5%) GSA Benefits at	58.00%	0
Indirect Cost at	0.00%	0
Total Cost		490,276
Contingency at	42.00%	205,916
Cost Plus Contingency		696,192

	Duration
ing RFP	20
ing RFP	10
nder Prepare Blank specifications	10
ng Proposal prep at vendor	20
h Proposal prep at vendor	20
g Proposal Evaluation	10
ing Proposal Evaluation	10
ing Contract	5
g Set Up	20
ishing Contract	10
Blanks	5
ate Blanks, Half size	100
o Testing	20
erently Measurement	20
ishing	100
ted Metrology	20
g	10
1 Metrology	20
to UVA	10



Advanced LIGO Cost Estimate Detail

WBS Number	12-06111
WBS Description	Pathfinder
Activity	CO-P0111
Description	SPF-Pathfinder-SPF
Location	Capital Project
Cost Code	12-06111

Duration	65 days
Estimated By	A. Billingsley
Last Modified On	07/12/2011

Line	HSF Item Code	Cost Category	LIGO Resource Code	Description	Estimator Comments or Vendor	Cost Basis	Quantity (Hrs EA)	Direct Labor (AA, B1-B6)		Contract Labor (G5)		Equipment (D1,D2)		Travel (E1,E2)		Material (G1-G4)		Subcontracts (G5)		Total Cost (\$)	Reference		
								Unit Cost (\$)	Total (\$)	Unit Cost (\$)	Total (\$)	Unit Cost (\$)	Total (\$)	Unit Cost (\$)	Total (\$)	Unit Cost (\$)	Total (\$)	Unit Cost (\$)	Total (\$)				
1	R2	Labor	FN	Turner		FF	507	15	22,815											22,815	CO-P02000		
2	R2	Labor	01	Other		FF	170	50	8,950											8,950	CO-P02000		
3	R2	Labor	S0	Scientist		FF	108	10	1,320											1,320	CO-P02000		
4	D2	Equip	D2	Small Pathfinder Blank cost - roll up of 4		HD	1					Rate	1500							1500	CO-P02000		
5	FF	Int Travel	FF	Deliver Mirrors to UWA, review specifications		HD	1						2075	2075						2075	CO-P02000		
6	G5	Contract	G5	polish 3 optics	CSIRO	VO	1									129,610	129,610			129,610	CO-P02000		
7	G5	Contract	G5	Polish 3 Mock cleaner mirrors	Way Precision	VO	1									68,115	68,115			68,115	CO-P02000		
8	G5	Contract	G5	Stamps	Time Tech	VO	1									2,000	2,000			2,000	CO-P02000		
9	G5	Contract	G5													200,000	200,000			200,000	CO-P02000		
																				100,055	481,255		
																				Staff Benefits at	25.00%	1921	
																				6) GBA Benefits at	58.00%	0	
																				Indirect Cost at	0.00%	0	
																				Total Cost		490,276	
																				Agency at	42.00%	205,916	
																				Agency		696,192	

Labor Summary (Direct Labor plus...)

Key/Fac	Post/Doc
Hours	
Person Years	

**WBS Definition**

In addition to serving as a summary fabrication associated with the R&D this WBS element. The purpose of industrial partners to achieve the following:

- Supply Blanks in the large for bulk absorption at 100% micro under WBS element 01-02-2 and enabling research to be able to fully requirements. The cost for the large proof of capability and the first size.
- Supply polishing to the FF the large sizes required. Initially provided by WBS element 01-02-2, this WBS element will be polishes on full scale optics.
- Coatings on large diameter absorption in the high reflectance qualification of a next coating vendor absorption at full scale size when research WBS element 01-02-2 coating prescription for a lower level of this small scale coating research production facility.

Task List

Task No	Description	Duration
CO-P50560	SPF- Polishing RFP	20
CO-P50600	SPF- Coating RFP	10
CO-D50540	Small Pathfinder-Prepare Blank specifications	10
CO-P50610	SPF - Coating Proposal prep at vendor	20
CO-P50570	SPF - Polish Proposal prep at vendor	20
CO-P50620	SPF-Coating Proposal Evaluation	10
CO-P50580	SPF-Polishing Proposal Evaluation	10
CO-P50630	SPF-Let Coating Contract	5
CO-T50640	SPF-Coating Set Up	20
CO-P50590	SPF-Let Polishing Contract	10
CO-P50550	SPF-Order Blanks	5
CO-F50650	SPF-Fabricate Blanks, Half size	100
CO-Q50660	SPF-Absorb Testing	20
CO-Q50670	SPF-Homogeneity Measurement	20
CO-F50680	SPF-PF-Polishing	120
CO-Q50690	SPF- Uncoated Metrology	20
CO-T50700	SPF-Coating	40
CO-Q50710	SPF-Coated Metrology	20
CO-H50720	SPF-Deliver to UWA	10




# Summary (Base Year Estimate)

## Advanced LIGO Cost Estimate Summary

WBS 11GO.4 Advanced LIGO

WBSNo	Description	Direct Labor Total		Contract Labor Total		Equipment Total (\$)	Travel Cost (\$)	Material Total (\$)	Subcontracts Total (\$)	Indirect Cost (\$)	SubTotal Cost (\$)	Contingency		Total Cost (\$)
		Hours	(\$)	Hours	(\$)							%	(\$)	
11GO.4.01	Facility Modifications (FAC)	2,432	197,631			1,404,640			1,774,283	51,384	3,427,938	22.00%	754,146	4,182,085
11GO.4.02	Seismic Isolation (SEI)	46,875	2,118,156			31,515,198	157,200		60,000	1,308,419	35,158,973	26.09%	9,172,353	44,331,327
11GO.4.03	Suspension (SUS)	124,250	5,321,805			19,770,570	743,300	27,500	694,400	4,195,632	30,753,207	27.12%	8,340,631	39,093,838
11GO.4.04	Prestabilized Laser (PSL)	41,520	2,572,135			8,894,894	250,000		128,000	2,316,728	14,161,757	22.00%	3,115,553	17,277,310
11GO.4.05	Input Optics (IO)	16,768	779,919			1,627,044	60,450		766,711	564,370	3,798,493	27.41%	1,041,280	4,839,773
11GO.4.06	Core Optics Components (COC)	20,898	900,646			6,205,533	186,550		5,876,029	674,061	13,842,819	43.91%	6,078,011	19,920,830
11GO.4.07	Auxiliary Optics (AOS)	94,472	3,830,860			3,114,360	393,050	1,091,360	991,051	2,483,390	11,904,070	26.55%	3,160,863	15,064,932
11GO.4.08	Interferometer Sensing and Control (ISC)	78,290	3,018,284			4,740,065	52,000			1,895,493	9,705,841	32.00%	3,105,869	12,811,710
11GO.4.09	Data Acq., Diags., Network & Supervisory Ctrl	33,836	2,463,483			3,080,500	225,000			1,737,229	7,506,212	22.00%	1,651,367	9,157,578
11GO.4.10	Support Equipment (SUP)					1,185,771				0	1,185,771	26.50%	314,229	1,500,000
11GO.4.12	LIGO Data Analysis System (LDAS)	52,952	2,294,153			6,657,000	20,000			1,434,775	10,405,928	20.00%	2,081,186	12,487,114
11GO.4.13	Installation (INS)	232,289	10,855,243	51,732	2,069,280	1,730,000	1,175,000			3,963,300	20,351,520	22.00%	4,477,336	24,828,856
11GO.4.14	Project Management (PM)	27,540	1,680,682	39,730	2,387,322		37,400			2,944,988	7,694,969	22.00%	1,692,893	9,387,862
		772,122	36,032,997	91,462	4,456,602	89,925,574	3,209,950	1,118,860	10,790,473	23,569,770	169,897,507	26.48%	44,985,718	214,883,225



LIGO-G030251-01-M


LIGO Laboratory



# Total Cost Profile

## Profile Data

	2000	2001	2002	2003	2004	2005	2006	2007	2008	2009	2010	2011	TOTAL	Total Cbook
Development	\$ 342,211	\$ 2,698,581	\$ 3,890,989	\$ 10,695,029	\$ 11,113,229	\$ 7,475,468	\$ 10,020,353	\$ 3,138,804	\$ 1,149,618	\$ 259,607	\$ 71,316	\$ -	\$ 50,855,405	
Fabrication(L)	\$ -	\$ -	\$ -	\$ 535,487	\$ 2,496,496	\$ 3,033,760	\$ 6,737,831	\$ 9,471,502	\$ 8,416,473	\$ 10,682,198	\$ 5,406,090	\$ -	\$ 47,079,837	
Fabrication	\$ -	\$ -	\$ -	\$ 4,249	\$ 5,233,581	\$ 14,827,432	\$ 33,589,385	\$ 29,968,068	\$ 25,227,342	\$ 7,841,298	\$ 256,695	\$ -	\$ 118,948,050	\$ 214,883,292
Escalation	\$ -	\$ -	\$ -	\$ -	\$ 565,299	\$ 1,561,273	\$ 4,668,579	\$ 5,343,951	\$ 5,541,724	\$ 3,644,904	\$ 1,318,120	\$ -	\$ 22,643,850	
<b>Cumulative</b>	<b>\$ 342,211</b>	<b>\$ 3,040,792</b>	<b>\$ 6,931,781</b>	<b>\$ 18,166,546</b>	<b>\$ 37,575,151</b>	<b>\$ 64,773,084</b>	<b>\$ 119,789,232</b>	<b>\$ 167,711,567</b>	<b>\$ 208,046,924</b>	<b>\$ 230,474,931</b>	<b>\$ 237,527,152</b>	<b>\$ 237,527,152</b>		



<b>Escalated CB</b>	<b>\$237,527,152</b>
ACIGA	(\$2,101,371)
UG (Pparc)	(\$12,388,443)
Albert Einstein Institute	(\$13,283,883)
GEO - SUS PD	(\$724,536)
<b>Subtotal</b>	<b>\$209,028,918</b>
Ops covers	(\$53,217,070)
Development	
Ops covers Fab Labor	(\$53,827,443)
Collaborator Labor Above	\$8,703,117
Collaborator Dev Non-Labor	\$1,449,479
New Labor	\$11,176,839
<b>Forecast of Request</b>	<b>\$123,313,839</b>
<b>NOTES</b>	
1. Included in the collaborator amounts are \$8,703,117 in labor and \$1,449,479 in non-labor through development. This is added back in after deduction of the operations contribution for Development and Fab Labor.	
2. New Labor included in the request is based upon identifying new labor specifically for Adv LIGO as contract labor. (See Cost Book Summary)	

	IFO	As Spent	Base Year
IFO 01	\$	133,697,288	\$ 123,485,780
IFO 02	\$	53,200,505	\$ 47,079,045
IFO 03	\$	50,629,352	\$ 44,318,459
<b>Grand Total</b>	<b>\$</b>	<b>237,527,145</b>	<b>\$ 214,883,284</b>

## As Spent Matrix

Phase	Sub System	Sub System														Grand Total
		AQS	CQC	COMP	DAQ	FAC	INS	IO	ISC	PSL	SEI	SUS	PM	SUP		
Ops / R&D		\$5,844,751	\$2,964,718	\$2,065,813	\$3,494,185	\$0	\$595,061	\$1,256,893	\$6,333,844	\$8,103,019	\$6,378,870	\$14,118,250	\$0	\$0	\$50,855,402	
MRE	Labor	\$2,780,593	\$820,848	\$2,432,903	\$2,062,914	\$303,801	\$20,345,103	\$825,123	\$2,220,903	\$1,340,224	\$1,179,387	\$3,654,087	\$9,313,945	\$0	\$47,079,841	
	Non Labor	\$6,639,587	\$16,235,268	\$7,988,400	\$3,600,464	\$3,878,286	\$3,888,696	\$2,957,759	\$4,257,000	\$7,834,077	\$36,773,074	\$21,321,511	\$73,919	\$1,500,000	\$116,948,041	
Escalation		\$1,231,778	\$1,167,580	\$1,877,977	\$761,922	\$441,209	\$4,132,071	\$473,183	\$1,875,595	\$964,573	\$4,157,146	\$4,689,299	\$683,263	\$188,263	\$22,643,858	
<b>Subtotal</b>		<b>\$16,296,709</b>	<b>\$21,088,412</b>	<b>\$14,365,093</b>	<b>\$9,919,485</b>	<b>\$4,623,296</b>	<b>\$28,960,931</b>	<b>\$5,312,958</b>	<b>\$14,687,342</b>	<b>\$18,241,893</b>	<b>\$48,488,487</b>	<b>\$43,783,147</b>	<b>\$10,071,127</b>	<b>\$1,688,263</b>	<b>\$237,527,142</b>	
GEO															(\$722,100)	
U. Glasgow															(\$2,283,648)	
U. Birmingham			(\$560,480)												(\$2,473,011)	
Rutherford															(\$6,098,653)	
Albert Einstein Institute															(\$12,435,506)	
ACIGA		(\$1,934,190)													(\$1,934,190)	
Escalation		(\$167,181)	(\$24,608)												(\$2,551,128)	
<b>Sutotal</b>		<b>\$14,195,337</b>	<b>\$20,503,324</b>	<b>\$14,365,093</b>	<b>\$9,919,485</b>	<b>\$4,623,296</b>	<b>\$27,950,398</b>	<b>\$5,312,958</b>	<b>\$14,687,342</b>	<b>\$4,958,010</b>	<b>\$48,488,487</b>	<b>\$32,265,788</b>	<b>\$10,071,127</b>	<b>\$1,688,263</b>	<b>\$209,028,909</b>	

**Cost Book Total**  
\$214,883,284


**Collaborator Total**  
(\$26,498,234)



# Request Profile

Request Profile As Spent Data

	2000	2001	2002	2003	2004	2005	2006	2007	2008	2009	2010	2011	TOTAL
Total As-Spent	\$ 342,211	\$ 2,698,581	\$ 3,890,989	\$ 11,234,765	\$ 19,408,606	\$ 27,197,933	\$ 55,016,148	\$ 47,922,335	\$ 40,335,357	\$ 22,428,007	\$ 7,052,221	\$ -	\$ 237,827,162
Contribution from Ops	(\$ (342,211))	(\$ (2,698,581))	(\$ (3,890,989))	(\$ (10,886,004))	(\$ (12,557,809))	(\$ (9,969,589))	(\$ (16,526,811))	(\$ (11,639,914))	(\$ (10,124,126))	(\$ (11,716,137))	(\$ (5,515,603))	\$ -	(\$ (35,957,674))
Collaborators	\$ -	\$ -	\$ -	\$ -	(\$ (317,512))	(\$ (4,140,055))	(\$ (5,073,644))	(\$ (1,929,845))	(\$ (5,763,453))	(\$ (1,121,133))	\$ -	\$ -	(\$ (18,345,641))
Request Amount	\$ -	\$ -	\$ -	\$ 348,761	\$ 6,533,184	\$ 13,068,298	\$ 33,415,993	\$ 34,362,676	\$ 24,447,778	\$ 9,590,738	\$ 1,536,618	\$ -	\$ 123,313,836
Cumulative	\$ -	\$ -	\$ -	\$ 348,761	\$ 6,881,946	\$ 19,970,233	\$ 53,386,126	\$ 87,738,703	\$ 112,186,481	\$ 121,777,218	\$ 123,313,836	\$ 123,313,836	\$ -



Escalated CB	\$237,527,152
ACIGA	(\$2,101,371)
UG (Pparc)	(\$12,368,443)
Albert Einstein Institute	(\$13,263,883)
GEO - SUS PD	(\$724,536)
<b>Subtotal</b>	<b>\$209,028,918</b>
Ops covers Development	(\$53,217,070)
Ops covers Fab Labor	(\$53,527,443)
Collaborator Labor Above	\$8,703,117
Collaborator Dev Non-Labor	\$1,449,479
New Labor	\$11,178,839
<b>Forecast of Request</b>	<b>\$123,313,839</b>

NOTES:  
 1. Included in the collaborator amounts are \$8,703,117 in labor and \$1,449,479 in non-labor through development. This is added back in after deduction of the operations contribution for Development and Fab Labor.  
 2. New Labor included in the request is based upon identifying new labor specifically for Adv LIGO as contract labor. (See Cost Book Summary)

	I/O	As Spent	Collaborators
I/O 01	\$	\$ 54,187,315	\$ (6,973,348)
I/O 02	\$	\$ 36,600,787	\$ (6,623,326)
I/O 03	\$	\$ 33,525,733	\$ (5,748,963)
<b>Grand Total</b>	\$	\$ 123,313,835	\$ (18,345,638)

Request Profile Base Yr. Adding Contingency and Escalation


	2000	2001	2002	2003	2004	2005	2006	2007	2008	2009	2010	2011	TOTAL
Total Base Yr \$	\$ 296,534	\$ 2,138,363	\$ 2,899,984	\$ 8,689,884	\$ 14,393,023	\$ 19,978,696	\$ 39,065,621	\$ 33,598,056	\$ 27,705,616	\$ 14,776,764	\$ 4,524,967	\$ -	\$ 168,088,559
Total Contingency	\$ 45,677	\$ 560,218	\$ 991,005	\$ 2,544,881	\$ 4,450,283	\$ 6,567,964	\$ 11,261,948	\$ 8,980,288	\$ 7,087,017	\$ 4,006,319	\$ 1,209,134	\$ -	\$ 46,794,734
Request Base Yr \$	\$ -	\$ -	\$ -	\$ 285,870	\$ 4,755,661	\$ 9,484,721	\$ 23,754,959	\$ 24,241,710	\$ 18,814,271	\$ 6,318,009	\$ 1,024,107	\$ -	\$ 86,579,308
Request Contingency	\$ -	\$ -	\$ -	\$ 62,891	\$ 1,587,236	\$ 2,852,246	\$ 6,825,317	\$ 6,280,109	\$ 4,274,597	\$ 1,714,083	\$ 225,304	\$ -	\$ 23,821,783
Request Escalation	\$ -	\$ -	\$ -	\$ -	\$ 190,287	\$ 751,321	\$ 2,835,617	\$ 3,630,757	\$ 3,358,910	\$ 1,558,646	\$ 287,207	\$ -	\$ 12,812,745
<b>Cumulative</b>	\$ -	\$ -	\$ -	\$ 348,761	\$ 6,881,946	\$ 19,970,233	\$ 53,386,126	\$ 87,738,703	\$ 112,186,481	\$ 121,777,218	\$ 123,313,836	\$ 123,313,836	\$ 123,313,836

Cost Book Check	\$214,893,292
Percentage Contingency	27.48%



# Bottom Up and Top Down Staffing Model

FTE Analysis



FTE Summary Graph Area	2000	2001	2002	2003	2004	2005	2006	2007	2008	2009	2010	2011
Total FTEs 1800 Hrs / Yr	2	9	16	32	45	50	65	74	68	80	41	0
From Ops / R&D - Staffing Plan	2	6	14.7	32.7	49.8	48.7	43.2	86.5	86.5	86.5	43.2	0
Collaborators	-0.72	-2.70	-1.34	-5.04	-5.77	-4.97	-10.68	-3.13	-4.85	-2.86	-0.13	0.00
Labor Included in the Request Amount	0.00	0.00	0.00	-1.27	-5.22	-5.20	-6.80	-11.29	-5.93	-8.04	-7.06	0.00
Total Planned FTEs (Total - Collab.- Labor in Request)	1	6	15	26	34	39	47	60	55	69	34	0


Ttl Hours Less Collaborators and Request	694429
Total Hours Staffing Plan	899640




---

# Schedule


# Level 1




# Level 2



# Level 3




# Level 4





# Level 5






---

# Performance Measurement




# Planning for Performance Measurement


- At what level do you cost load the schedule?
  - » WBS Level is where we collect actual cost.
  - » Cost Book Activity Sheet is where we load the estimate.
  - » Schedule Activity level is where we measure progress that determines the earned value.
- Performance Evaluation is executed at the rollup level for the WBS.
  - » BCWS – baseline plan
  - » BCWP - performance
  - » ACWP – actual costs
  - » Schedule Variance
  - » Cost Variance



Activity ID	Activity Description	Orig Dur	Early Start	Early Finish	Total Float	Budgeted Cost	% Comp	2001	2002	2003	2004	2005	2006	2007
<b>LIGO</b>														
<b>LIGO.4 Advanced LIGO Construction</b>														
Subtotal		1,006	18OCT00A	25OCT04	0	2,162,299.54	37							
<b>LIGO.4.06 Core Optics Components (COC)</b>														
<b>LIGO.4.06.4 COC Fabrication</b>														
<b>LIGO.4.06.4.1 Pathfinder</b>														
CO-W40641	WBS: COC Pathfinder	1,006	18OCT00A	25OCT04	0	0.00	36							
CO-F40641A	EST: Pathfinder SPF	654*	18OCT00A	02JUN03	108	696,192.27	55							
CO-F40641B	EST: Pathfinder LPF	986*	15NOV00A	25OCT04	-244	1,466,107.27	37							
CO-D50540	Small Pathfinder-Prepare Blank specifications	10	18OCT00A	31OCT00A		0.00	100							
CO-P50550	SPF-Order Blanks	5	02JAN02A	08JAN02A		0.00	100							
CO-P50560	SPF- Polishing RFP	20	18OCT00A	14NOV00A		0.00	100							
CO-P50570	SPF - Polish Proposal prep at vendor	20	15NOV00A	14DEC00A		0.00	100							
CO-P50580	SPF-Polishing Proposal Evaluation	10	15DEC00A	02JAN01A		0.00	100							
CO-P50590	SPF-Let Polishing Contract	10	03JAN01A	17JAN01A		0.00	100							
CO-P50600	SPF- Coating RFP	10	18OCT00A	31OCT00A		0.00	100							
CO-P50610	SPF - Coating Proposal prep at vendor	20	01NOV00A	30NOV00A		0.00	100							
CO-P50620	SPF-Coating Proposal Evaluation	10	01DEC00A	14DEC00A		0.00	100							
CO-P50630	SPF-Let Coating Contract	5	15DEC00A	21DEC00A		0.00	100							
CO-T50640	SPF-Coating Set Up	20	22DEC00A	24JAN01A		0.00	100							
CO-F50650	SPF-Fabricate Blanks, Half size	100	09JAN02A	31MAY02	108	0.00	57							
CO-Q50660	SPF-Absorb Testing	20	03JUN02	28JUN02	108	0.00	0							
CO-Q50670	SPF-Homogeneity Measurement	20	01JUL02	29JUL02	108	0.00	0							
CO-F50680	SPF-PF-Polishing	120	30JUL02	23JAN03	108	0.00	0							
CO-Q50690	SPF- Uncoated Metrology	20	24JAN03	21FEB03	108	0.00	0							
CO-T50700	SPF-Coating	40	24FEB03	18APR03	108	0.00	0							
CO-Q50710	SPF-Coated Metrology	20	21APR03	16MAY03	108	0.00	0							
CO-H50720	SPF-Deliver to UWA	10	19MAY03	02JUN03	108	0.00	0							
CO-D50740	LPF-Prepare Blank specifications Full size	10	15NOV00A	30NOV00A		0.00	100							
CO-P50750	LPF-Order Blanks - Pathfinder full size	10	01DEC00A	14DEC00A		0.00	100							
CO-P50760	LPF- Polishing RFP	10	03DEC03	16DEC03	-244	0.00	0							
CO-P50770	LPF - Polish Proposal prep at vendor	10	17DEC03	05JAN04	-244	0.00	0							
CO-P50780	LPF-Let Polishing Contract	10	06JAN04	20JAN04	-244	0.00	0							
CO-P50790	LPF- Coating RFP	10	03DEC03	16DEC03	-164	0.00	0							
CO-P50800	LPF - Coating Proposal prep at vendor	10	17DEC03	05JAN04	-164	0.00	0							
CO-P50810	LPF-Let Coating Contract	5	06JAN04	12JAN04	-164	0.00	0							
CO-T50820	LPF-Coating Set Up	20	13JAN04	10FEB04	-164	0.00	0							
CO-F50830	LPF-Fabricate Blanks, Full size	260	09NOV01A	26DEC02	-20	0.00	36							
CO-Q50840	LPF-Absorb Testing	20	27DEC02	28JAN03	-20	0.00	0							
CO-Q50850	LPF-Homogeneity Measurement	20	29JAN03	26FEB03	-20	0.00	0							
CO-F50860	LPF-Polishing	80	21JAN04	12MAY04	-244	0.00	0							
CO-Q50870	LPF- Uncoated Metrology	15	13MAY04	03JUN04	-244	0.00	0							
CO-F50880	LPF-Coating	80	04JUN04	27SEP04	-244	0.00	0							
CO-Q50890	LPF-Coated Metrology	20	28SEP04	25OCT04	-244	0.00	0							
CO-H50900	Deliver LPF ETM to LASTI	0		25OCT04	-244	0.00	0							




Activity ID	Activity Description	Orig Dur	Early Start	Early Finish	Total Float	Budgeted Cost	% Comp	R/C % Expended	Cost to Date (ACWP)	Planned value cost (BCWS)	Earned value cost (BCWP)	Cost at Completion	Sched Var (BCWP - BCWS)	Cost Variance (BCWP - ACWP)
<b>LIGO</b>														
<b>LIGO.4 Advanced LIGO Construction</b>														
Subtotal		1.006	18OCT00A	25OCT04	0	2,162,299.54	37	69	1,500,000.00	1,058,066.66	920,893.41	2,162,299.54	-137,173.25	-579,106.59
<b>LIGO.4.06 Core Optics Components (COC)</b>														
<b>LIGO.4.06.4 COC Fabrication</b>														
<b>LIGO.4.06.4.1 Pathfinder</b>														
CO-W40641	WBS: COC Pathfinder	1.006	18OCT00A	25OCT04	0	0.00	36	0	1,500,000.00	0.00	0.00	2,162,299.54	0.00	-1,500,000.00
CO-F40641A	EST: Pathfinder SPF	654	18OCT00A	02JUN03	108	696,192.27	55	0	0.00	384,289.61	384,298.14	0.00	6.53	384,298.14
CO-F40641B	EST: Pathfinder LPF	986	15NOV00A	25OCT04	-244	1,466,107.27	37	0	0.00	673,777.05	536,595.27	0.00	-137,181.78	536,595.27
CO-D50540	Small Pathfinder-Prepare Blank specifications	10	18OCT00A	31OCT00A		0.00	100	0	0.00	0.00	0.00	0.00	0.00	0.00
CO-P50550	SPF-Order Blanks	5	02JAN02A	08JAN02A		0.00	100	0	0.00	0.00	0.00	0.00	0.00	0.00
CO-P50560	SPF- Polishing RFP	20	18OCT00A	14NOV00A		0.00	100	0	0.00	0.00	0.00	0.00	0.00	0.00
CO-P50570	SPF - Polish Proposal prep at vendor	20	15NOV00A	14DEC00A		0.00	100	0	0.00	0.00	0.00	0.00	0.00	0.00
CO-P50580	SPF-Polishing Proposal Evaluation	10	15DEC00A	02JAN01A		0.00	100	0	0.00	0.00	0.00	0.00	0.00	0.00
CO-P50590	SPF-Let Polishing Contract	10	03JAN01A	17JAN01A		0.00	100	0	0.00	0.00	0.00	0.00	0.00	0.00
CO-P50600	SPF - Coating RFP	10	18OCT00A	31OCT00A		0.00	100	0	0.00	0.00	0.00	0.00	0.00	0.00
CO-P50610	SPF - Coating Proposal prep at vendor	20	01NOV00A	30NOV00A		0.00	100	0	0.00	0.00	0.00	0.00	0.00	0.00
CO-P50620	SPF-Coating Proposal Evaluation	10	01DEC00A	14DEC00A		0.00	100	0	0.00	0.00	0.00	0.00	0.00	0.00
CO-P50630	SPF-Let Coating Contract	5	15DEC00A	21DEC00A		0.00	100	0	0.00	0.00	0.00	0.00	0.00	0.00
CO-T50640	SPF-Coating Set Up	20	22DEC00A	24JAN01A		0.00	100	0	0.00	0.00	0.00	0.00	0.00	0.00
CO-F50650	SPF-Fabricate Blanks, Half size	100	09JAN02A	31MAY02	108	0.00	57	0	0.00	0.00	0.00	0.00	0.00	0.00
CO-Q50660	SPF-Absorb Testing	20	03JUN02	28JUN02	108	0.00	0	0	0.00	0.00	0.00	0.00	0.00	0.00
CO-Q50670	SPF-Homogeneity Measurement	20	01JUL02	29JUL02	108	0.00	0	0	0.00	0.00	0.00	0.00	0.00	0.00
CO-F50680	SPF-PF-Polishing	120	30JUL02	23JAN03	108	0.00	0	0	0.00	0.00	0.00	0.00	0.00	0.00
CO-Q50690	SPF- Uncoated Metrology	20	24JAN03	21FEB03	108	0.00	0	0	0.00	0.00	0.00	0.00	0.00	0.00
CO-T50700	SPF-Coating	40	24FEB03	18APR03	108	0.00	0	0	0.00	0.00	0.00	0.00	0.00	0.00
CO-Q50710	SPF-Coated Metrology	20	21APR03	16MAY03	108	0.00	0	0	0.00	0.00	0.00	0.00	0.00	0.00
CO-H50720	SPF-Deliver to UWA	10	19MAY03	02JUN03	108	0.00	0	0	0.00	0.00	0.00	0.00	0.00	0.00
CO-D50740	LPF-Prepare Blank specifications Full size	10	15NOV00A	30NOV00A		0.00	100	0	0.00	0.00	0.00	0.00	0.00	0.00
CO-P50750	LPF-Order Blanks - Pathfinder full size	10	01DEC00A	14DEC00A		0.00	100	0	0.00	0.00	0.00	0.00	0.00	0.00
CO-P50760	LPF- Polishing RFP	10	03DEC03	16DEC03	-244	0.00	0	0	0.00	0.00	0.00	0.00	0.00	0.00
CO-P50770	LPF - Polish Proposal prep at vendor	10	17DEC03	05JAN04	-244	0.00	0	0	0.00	0.00	0.00	0.00	0.00	0.00
CO-P50780	LPF-Let Polishing Contract	10	06JAN04	20JAN04	-244	0.00	0	0	0.00	0.00	0.00	0.00	0.00	0.00
CO-P50790	LPF- Coating RFP	10	03DEC03	16DEC03	-164	0.00	0	0	0.00	0.00	0.00	0.00	0.00	0.00
CO-P50800	LPF - Coating Proposal prep at vendor	10	17DEC03	05JAN04	-164	0.00	0	0	0.00	0.00	0.00	0.00	0.00	0.00
CO-P50810	LPF-Let Coating Contract	5	06JAN04	12JAN04	-164	0.00	0	0	0.00	0.00	0.00	0.00	0.00	0.00
CO-T50820	LPF-Coating Set Up	20	13JAN04	10FEB04	-164	0.00	0	0	0.00	0.00	0.00	0.00	0.00	0.00
CO-F50830	LPF-Fabricate Blanks, Full size	260	09NOV01A	26DEC02	-20	0.00	36	0	0.00	0.00	0.00	0.00	0.00	0.00
CO-Q50840	LPF-Absorb Testing	20	27DEC02	28JAN03	-20	0.00	0	0	0.00	0.00	0.00	0.00	0.00	0.00
CO-Q50850	LPF-Homogeneity Measurement	20	29JAN03	28FEB03	-20	0.00	0	0	0.00	0.00	0.00	0.00	0.00	0.00
CO-F50860	LPF-Polishing	80	21JAN04	12MAY04	-244	0.00	0	0	0.00	0.00	0.00	0.00	0.00	0.00
CO-Q50870	LPF- Uncoated Metrology	15	13MAY04	03JUN04	-244	0.00	0	0	0.00	0.00	0.00	0.00	0.00	0.00
CO-F50880	LPF-Coating	80	04JUN04	27SEP04	-244	0.00	0	0	0.00	0.00	0.00	0.00	0.00	0.00
CO-Q50890	LPF-Coated Metrology	20	28SEP04	25OCT04	-244	0.00	0	0	0.00	0.00	0.00	0.00	0.00	0.00
CO-H50900	Deliver LPF ETM to LASTI	0		25OCT04	-244	0.00	0	0	0.00	0.00	0.00	0.00	0.00	0.00



Resource Profile/Table

Select... Resources: Total

Display... Previous Next





# Progress Data Collection

- Primavera Project Planner Post Office.
  - » A built in feature within the application creates a mail attachment that contains the activities to be updated.
- Excel spreadsheets can be easily imported.

The screenshot shows the 'Primavera Post Office - COCM' dialog box. It contains the following text:

Below is a list of your activities.

Please update these activities to indicate their status through:

If you started an activity, check the box in the Started? column, enter the start date, and enter a value in the Percent Complete column.

If you finished an activity, check the box in the Finished? column and enter a finish date. The percent complete automatically shows 100.

The dialog box also includes buttons for OK, Cancel, Help, and Print... and a date field set to 05/01/2002.


Below the dialog box is an Excel spreadsheet with the following data:

Activity ID	Description	Started?	Start Date	Finished?	Finish Date	Percent Complete
CO-D50540	Small Pathfinder-Prepare Blank spe	<input checked="" type="checkbox"/>	10/18/2000	<input checked="" type="checkbox"/>	10/31/2000	100.0
CO-F50650	SPF-Fabricate Blanks, Half size	<input checked="" type="checkbox"/>	01/09/2002	<input type="checkbox"/>		57.0
CO-F50680	SPF-PF-Polishing	<input type="checkbox"/>		<input type="checkbox"/>		0.0
CO-H50720	SPF-Deliver to UWA	<input type="checkbox"/>		<input type="checkbox"/>		0.0
CO-P50550	SPF-Order Blanks	<input checked="" type="checkbox"/>	01/02/2002	<input checked="" type="checkbox"/>	01/08/2002	100.0
CO-P50560	SPF- Polishing RFP	<input checked="" type="checkbox"/>	10/18/2000	<input checked="" type="checkbox"/>	11/14/2000	100.0
CO-P50570	SPF - Polish Proposal prep at vendc	<input checked="" type="checkbox"/>	11/15/2000	<input checked="" type="checkbox"/>	12/14/2000	100.0
CO-P50580	SPF-Polishing Proposal Evaluation	<input checked="" type="checkbox"/>	12/15/2000	<input checked="" type="checkbox"/>	01/02/2001	100.0
CO-P50590	SPF-Let Polishing Contract	<input checked="" type="checkbox"/>	01/03/2001	<input checked="" type="checkbox"/>	01/17/2001	100.0

The spreadsheet also includes a list of activities with columns for Activity #, Activity, and various dates and percentages.

COST ACCOUNT	PCT COM	CUMULATIV ACWP	CUMULATIV BCWP	CUMULATIV BCWS	COST VARIANCE	SCHEDULE VARIANCE	BUDGETED COST	COST AT COMPLETIO	CAC VARIANCE
07-4131-04	100	75000	90000	90000	15000	0	90000	75000	15000
07-4133-04	37	235250	238125	385938	2875	-147812	637500	735150	-97650
07-4134-04	39	234375	234375	435385	0	-201010	600000	837000	-237000
07-4135-04	0	0	0	0	0	0	225000	225000	0
07-4136-04	69	392000	416250	464423	24250	-48173	600000	850000	-250000
07-4137-04	0	0	0	0	0	0	112500	112500	0
		<b>936625</b>	<b>978750</b>	<b>1375745</b>	<b>42125</b>	<b>-396995</b>	<b>2265000</b>	<b>2834650</b>	<b>-569650</b>

### Trend Analysis LIGO II Model







# Milestone Model


Activity ID	Activity Description	Org. Div.	Early Start	Early Finish	Link Start	Link Finish	Total Float	2003	2004	2005	2006	2007	2008	2009	2010
<b>LIGO</b>															
<b>LIGO.4 Advanced LIGO</b>															
<b>LIGO.4.01 Facility Modifications (FAC)</b>															
<b>LIGO.4.01.1 FAC Vacuum Equipment</b>															
<b>LIGO.4.01.1.2 Clean Room Systems</b>															
11A00110	Install Air FE-8 GSE assembly			01/01/06		01/01/07	31								
<b>LIGO.4.02 Seismic Isolation (SEI)</b>															
<b>LIGO.4.02.1 SEI Subsystem Management</b>															
01M0000	SEI Project Start		01/01/03				308								
01M0000	SEI Project Finish			01/01/06			0								
<b>LIGO.4.02.3 SEI Design</b>															
<b>LIGO.4.02.3.1 SEI Conceptual Design/Requirements</b>															
01M0200	Seismic Isolation Design Req. Review (DR)			01/01/03		01/01/03	0								
<b>LIGO.4.02.3.2 SEI Preliminary Design</b>															
01M0200	Seismic Isolation Prelim. Design Rev. (PDR)			01/01/03		01/01/03	0								
<b>LIGO.4.02.3.2.2 LASTI HAM Unit</b>															
<b>LIGO.4.02.3.2.2.3 Procurement / Contracts</b>															
<b>LIGO.4.02.3.2.2.3.2 Mech. Contract Solicitation / Revs.</b>															
01T0200	SEI PD HAM Kick Off Meeting			01/01/03		01/01/03	0								
<b>LIGO.4.02.3.2.2.3.8 Test</b>															
01C0300	SEI PD HAM Prepare Report			01/01/03		01/01/03	0								
<b>LIGO.4.02.3.2.2.7 Operation Control Development</b>															
01C0400	SEI PD HAM Prepare Report			01/01/03		01/01/03	0								
<b>LIGO.4.02.3.2.3 LASTI BSC Unit</b>															
<b>LIGO.4.02.3.2.3.3 Procurement / Contracts</b>															
<b>LIGO.4.02.3.2.3.3.2 Mech. Contract Solicitation / Revs.</b>															
01T0400	SEI PD BSC Kick Off Meeting			01/01/03		01/01/03	0								
<b>LIGO.4.02.3.2.3.8 Test</b>															
01C0400	SEI PD BSC Prepare Report			01/01/03		01/01/03	0								
<b>LIGO.4.02.3.2.3.7 Operation Control Development</b>															
01C0400	SEI PD BSC Prepare Report			01/01/03		01/01/03	0								
<b>LIGO.4.02.3.2.4 Preliminary Design Update / Integration</b>															
01C0400	SEI PD Preliminary Design Review			01/01/03		01/01/03	0								
<b>LIGO.4.02.3.3 SEI Final Design</b>															
01M0300	Seismic Isolation Final Design Rev. (FDR)			01/01/03		01/01/03	0								
<b>LIGO.4.02.3.3.1 Design</b>															
<b>LIGO.4.02.3.3.1.1 Requirements Update</b>															
01C0400	SEI PD Final Design Review			01/01/03		01/01/03	0								
<b>LIGO.4.02.4 SEI Fabrication</b>															
<b>LIGO.4.02.4.2 Assembly</b>															
<b>LIGO.4.02.4.2.2 HAM Assembly</b>															
01C0400	SEI PD HAM Assembly install contents			01/01/03		01/01/03	491								
01C0400	SEI PD HAM Assembly install contents			01/01/03		01/01/03	151								
01C0400	SEI PD HAM Assembly install contents			01/01/03		01/01/03	0								



# Major Milestones

---

Milestone	Date at End of Quarter Per Calendar Year
NSF Early Funding for Core Optics Available	5 Apr 2004
NSF Funding for Advanced LIGO Construction Available	4 Apr 2005
Installation begins at Livingston	8 Mar 2007
Installation begins at Hanford	15 Nov 2007
Commissioning begins at Livingston	15 Jun 2009
Commissioning begins at Hanford	30 Sep 2009
Livingston Operational	6 Jan 2010
Hanford Operational	22 Sep 2010





	Orig. Dtg.	Early Start	Early Finish	Budgeted Cost	Gantt Chart (FY00 to FY11)																																																
					FY00				FY01				FY02				FY03				FY04				FY05				FY06				FY07				FY08				FY09				FY10				FY11				
<b>LIGO Laboratory Program</b>																																																					
<b>IFO 01</b>		2,524	21AUG00	22SEP10	214,883,284.00																																																
<i>Summary</i>		2,524	21AUG00	22SEP10	129,485,780.00																																																
<b>+ Project Management</b>		1,061	01OCT03	28DEC07	9,387,894.00																																																
<b>+ Facility Modifications</b>		935	18FEB05	10NOV06	1,582,585.00																																																
<b>+ Seismic Isolation</b>		2,088	18OCT00	29FEB09	17,509,723.00																																																
<b>+ Suspension</b>		2,503	20SEP00	22SEP10	23,202,228.00																																																
<b>+ Prestabilized Laser</b>		1,793	28NOV00	13DEC07	11,621,440.00																																																
<b>+ Input Optics</b>		2,288	21AUG00	08OCT09	2,641,357.00																																																
<b>+ Core Optics</b>		1,718	18OCT00	30AUG07	12,512,416.00																																																
<b>+ Auxiliary Optics</b>		1,502	17JUN02	17JUN08	9,128,011.00																																																
<b>+ Interferometer Sensing and Control</b>		1,881	17JUN02	21DEC09	8,493,145.00																																																
<b>+ Data Acquisition and Diagnostics</b>		1,015	02JUN03	14SEP07	5,426,711.00																																																
<b>+ Support Equipment</b>		180	02JAN07	28SEP07	1,500,000.00																																																
<b>+ Computing and Data Analysis</b>		1,097	01APR05	18AUG09	10,055,452.00																																																
<b>+ Installation</b>		1,849	24FEB04	22SEP10	10,324,445.00																																																
<b>IFO 02</b>		1,309	11FEB05	06MAY10	47,079,045.00																																																
<i>Summary</i>		895	18FEB05	15SEP08	1,332,408.00																																																
<b>+ Facility Modifications</b>		895	18FEB05	15SEP08	1,332,408.00																																																
<b>+ Seismic Isolation</b>		490	27JUL05	11JUL08	13,491,895.00																																																
<b>+ Suspension</b>		350	12NOV07	09APR09	8,332,580.00																																																
<b>+ Prestabilized Laser</b>		413	26OCT05	22JUN07	2,831,840.00																																																
<b>+ Input Optics</b>		656	07AUG06	23MAR09	1,104,875.00																																																
<b>+ Core Optics</b>		497	11FEB05	07FEB07	3,080,487.00																																																







---

# Support of PPARC Proposal



# Real World Example – PPARC Proposal Support

## Advanced LIGO Cost Estimate Summary (UG, UB, RAL)

WBS LIGO.4 Advanced LIGO Construction

WBSNo	Description	Direct Labor		Contract Labor		Equipment Total (\$)	Travel Cost (\$)	Material Total (\$)	Subcontracts Total (\$)	Indirect Cost (\$)	SubTotal Cost (\$)	Contingency		Total Cost (\$)
		Hours	Total (\$)	Hours	Total (\$)							%	(\$)	
LIGO.4.03	Suspension (SUS)	20 257	989 463			4 925 450	202,700		300 000	521 528	6 939,140	24.89%	1,726,910	8,666,050
LIGO.4.06	Core Optics Components (COC)					391 944				0	391,944	43.00%	168,536	560,480
LIGO.4.13	Installation (INS)	3 840	209 500				396,000			157,430	762,930	5.00%	38,146	801,076
		24 097	1 198 963			5 317 394	598,700		300 000	678,958	8 094,014	23.89%	1,933,592	10,027,606

## Advanced LIGO Cost Estimate Detail (UG, UB, RAL)

WBS Number	LIGO.4.03.1
WBS Description	SUS Subsystem Management
Activity	SUL50030B
Description	SUS Sub System Management (UG, UB, RAL)
Location	Capital Project
Cost Code	12 4031 11

Duration	1215 days
Estimated By	T. Frey
Last Modified On	06/15/2002

Line	NSF Item Code	Cost Category	LIGO Resource Code	Description	Estimator Comments or Vendor	Cost Basis	Quantity (Hrs Ea)	Direct Labor (A4, B1-B6)		Contract Labor (C5)		Equipment (D1, D2)		Travel (E1, E2)		Material (F1-F4)		Subcontracts (G5)		Total Cost (\$)	Reference	
								Unit Cost (\$)	Total (\$)	Unit Cost (\$)	Total (\$)	Unit Cost (\$)	Total (\$)	Unit Cost (\$)	Total (\$)	Unit Cost (\$)	Total (\$)	Unit Cost (\$)	Total (\$)			Unit Cost (\$)
1	B2	Labor	SE	Senior Engineer		HD	1500	79	118,500												118,500	
2	E1	Inf Travel	E1	Travel Budget for Subsystem Mgmt	10 Trips / 1 week	HD	16							3,000	30,000						30,000	
Subtotal: SUL50030B SUS-Sub System Management (UG, UB,								118,500						30,000							148,500	

### Labor Summary (Direct Labor plus Contract Labor)

	AA	B1	B2	B3	B4	B5	Total	Grad	UGrad	Admin
Key/Fac										
Post/Doc										
Mgmt										
St/Sci										
Sci										
St/Engr							1500			
Engr										
Tech										
Other										
Total							1500			
Hours							0.8			
Person Years							0.8			

Risk Factors	Risk Multipliers
Technical 3	2.00%
Cost 2	1.00%
Schedule 2	1.00%
Calculated Contingency	16.00%
Estimator Override	

Staff Benefits at 0.00%	0
(56) G&A Benefits at 0.00%	0
Indirect Cost at 0.00%	0
Total Cost	148,500
Contingency at 16.00%	11,850
Cost Plus Contingency	160,350

**WBS Definition**  
 Technical management of the subsystem is covered in this WBS element. This is a level of effort task (the level may vary according to the development phase).

**Basis of Estimate**  
 Labor: Hours estimated based on historical data  
 Travel: Estimated based on historical data


**Task List**

Task No	Description	Duration
SUL50030	SUS Sub System Management	1215



# PPARC Proposal Example

- Using the schedule, we coded the tasks that represent the collaborator's scope.
- Using the cost book Access database, we cost loaded the schedule and generated cost profiles.








# PPARC Proposal Example

- Using the cost loaded schedule, we exported the cost profile data to a spread sheet in base year dollars.
- Using MS Excel, we generated a cost profile by GB Fiscal Years and applied an escalation rate.





---

# Partners and Management



# Partners and Management

---

- Principal fiduciary management will come from the LIGO Laboratory
- Advanced LIGO will be implemented with full LSC participation
- Capital partners (UK GEO, German GEO, ACIGA) will have a role in the project management
  - » Possible Institutional Board
  - » Details to be worked out as commitments defined
  - » Discussions between LIGO Lab and UK GEO/PPARC regarding nature and level of formal agreement
- Basic project management methods will follow the LIGO model



# Summary

---

- Experienced LIGO Lab team has planned and estimated Advanced LIGO
- LIGO Lab and LSC have formed a strong partnership
- Design and development process is already underway in a “project” setting
- Most of the elements of a formal project are in place
- Costs are estimated in detail
- Schedule planning is thorough and will support definition of the final negotiated project
- Performance measurement infrastructure is in place
- International partnerships are already being exercised
- Project Management Plan can be made definitive when financial commitments are complete



# Advanced LIGO In Context

---

- LIGO construction is complete
  - » NSF investment in LIGO now totals about \$400 million
  - » Construction cost \$292 million
  - » LIGO facilities represent ~ 2/3 of the construction investment and are intended to support successive detectors
- Initial LIGO detectors are operating and have carried out early scientific running
  - » Initial LIGO should accomplish its sensitive observation goal by late 2006
- Advanced LIGO development is defining the detailed design and retiring risks
- The experienced LIGO team will be ready to install Advanced LIGO in 2007
- Observations for probable gravitational wave detection can commence in 2010