

The LIGO Instruments






Stan Whitcomb

NSB Meeting
LIGO Livingston Observatory
4 February 2004




The Detection Challenge






Initial Interferometer Design Noise Budget

- Understanding of noise sources developed with 40 m prototype
- Limiting noise (with available technology)
 - » Seismic at low frequencies
 - » Thermal at mid frequencies
 - » Shot noise at high frequencies
- •Facility limits much lower to allow improved detectors as technology matures





Optical Configuration






Stabilized Laser



Custom-built
10 W Nd:YAG
laser—
Now a commercial
product





LIGO Optics

Substrates: SiO₂

High purity, low absorption

Polishing


Accuracy < 1 nm (~10 atomic diameters)
Micro-roughness < 0.1 nm (1 atom)

Coating

Scatter < 50 ppm
Absorption < 0.5 ppm
Uniformity <10⁻³ (~1 atom/layer)

Worked with industry to develop required technologies

2 manufacturers of fused silica
4 polishers
5 metrology companies/labs
1 optical coating company





Optics Suspension and Control



- Suspension is the key to controlling thermal noise
- Magnets and coils to control position and angle of mirrors







Core Optics Installation and Alignment



 Cleanliness of paramount importance





Seismic Isolation

 Cascaded stages of masses on springs (same principle as car suspension)






LIGO

Seismic Isolation













Commissioning Progress

Strain Sensitivity for the LLO 4km Interferometer





Science Runs as Sensitivity Improves




S3 Duty Cycle	
Hanford 4km	69%
Hanford 2km	63%
Livingston 4 km	22%*

* Limited by high ground noise



Seismic Environment at LLO

Test at MIT



- Anthropogenic ground vibrations
 - » Related to human activity mostly logging
- Microseism due to ocean waves
- Strategy for recovering full-time duty at LLO
 - » Use Hydraulic External Pre-Isolator (HEPI) system developed for AdvLIGO
 - » Prototype tested at Stanford and MIT
 - » Fabrication nearly complete, installation just beginning



Summary

- Jump from laboratory-scale to kilometer-scale interferometers has been successful
- Commissioning on track
 - » Sensitivity nearing design level
 - » Reliability and duty cycle as expected for this stage
 - » Active seismic isolation development addresses excess seismic noise at LLO, as well as Advanced LIGO requirements
- Interleaving of Science Runs with commissioning
 - » Science begins
 - » Analysis community prepares for full operation
 - Development of analysis algorithms, grid computing, ...